

RECEIVED

JAN 27 2004

Form 3160-3
(September 2001)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

DIV. OF OIL, GAS & MINING

FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. U-16540
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name N/A
2. Name of Operator Inland Production Company		7. If Unit or CA Agreement, Name and No. Eign 17-11-11
3a. Address Route #3 Box 3630, Myton UT 84052	3b. Phone No. (include area code) (435) 646-3721	8. Lease Name and Well No. Federal 11-7-9-18
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NE/SW 1980' FSL 1977' FWL 4432920 Y 40.04354 At proposed prod. zone 590618 X -109.93774		9. API Well No. 43-047-35451
10. Field and Pool, or Exploratory Eight Mile Flat		11. Sec., T., R., M., or Blk. and Survey or Area NE/SW Sec. 7, T9S R18E
12. Distance in miles and direction from nearest town or post office* Approximatley 17.8 miles southeast of Myton, Utah		12. County or Parish Uintah
13. State UT		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) Approx. 1977' f/lse, NA f/unit	16. No. of Acres in lease 1356.44	17. Spacing Unit dedicated to this well 40 Acres
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 1977'	19. Proposed Depth 6500'	20. BLM/BIA Bond No. on file #4488944
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 5072' GL	22. Approximate date work will start* 2nd Quarter 2004	23. Estimated duration Approximately seven (7) days from spud to rig release.
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

- | | |
|---|--|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the authorized officer. |

25. Signature <i>Mandie Crozier</i>	Name (Printed/Typed) Mandie Crozier	Date 1/26/04
Title Regulatory Specialist		
Approved by (Signature) <i>Bradley G. Hill</i>	Name (Printed/Typed) BRADLEY G. HILL	Date 01-28-04
Title Environmental Scientist III		

Federal Approval of this
Action is Necessary

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.


Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

T9S, R18E, S.L.B.&M.

INLAND PRODUCTION COMPANY

WELL LOCATION, FEDERAL 11-7-9-18,
LOCATED AS SHOWN IN THE NE 1/4 SW
1/4 OF SECTION 7, T9S, R18E, S.L.B.&M.
UINTAH COUNTY, UTAH.



THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF.



TRI STATE LAND SURVEYING & CONSULTING
180 NORTH VERNAL AVE. - VERNAL, UTAH 84078
(435) 781-2501

◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (PARIETTE DRAW SW)

SCALE: 1" = 1000'	SURVEYED BY: G.S.
DATE: 10-8-03	DRAWN BY: J.R.S.
NOTES:	FILE #

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

January 28, 2004

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2004 Plan of Development Eight Mile Flat
Unit, Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2004 within the Eight Mile Flat Unit, Uintah County, Utah.

API#	WELL NAME	LOCATION
(Proposed PZ Green River)		
43-047-35448	Federal 3-7-9-18 Sec 7 T09S R18E	0703 FNL 2104 FWL
43-047-35449	Federal 5-7-9-18 Sec 7 T09S R18E	2125 FNL 0745 FWL
43-047-35450	Federal 7-7-9-18 Sec 7 T09S R18E	1981 FNL 1981 FEL
43-047-35451	Federal 11-7-9-18 Sec 7 T09S R18E	1980 FSL 1977 FWL
43-047-35452	Federal 13-7-9-18 Sec 7 T09S R18E	0660 FSL 0660 FWL

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Eight Mile Flat Unit
Division of Oil Gas and Mining
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:1-28-04



January 26, 2004

State of Utah
Division of Oil, Gas & Mining
Attn: Diana Whitney
1594 West North Temple - Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RECEIVED

JAN 27 2004

DIV. OF OIL, GAS & MINING

RE: Applications for Permit to Drill: Federal 1-7-9-18, 3-7-9-18, 5-7-9-18, 7-7-9-18, 11-7-9-18, and 13-7-9-18.

Dear Diana:

Enclosed find APD's on the above referenced wells. If you have any questions, feel free to give either Brad or myself a call.

Sincerely,


Mandie Crozier
Regulatory Specialist

mc
enclosures

**INLAND PRODUCTION COMPANY
FEDERAL #11-7-9-18
NE/SW SECTION 7, T9S, R18E
UINTAH COUNTY, UTAH**

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. GEOLOGIC SURFACE FORMATION:

Uinta formation of Upper Eocene Age

2. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:

Uinta	0' – 1640'
Green River	1640'
Wasatch	5825'

3. ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:

Green River Formation 1640' – 6500' - Oil

4. PROPOSED CASING PROGRAM

Please refer to the Monument Butte Field Standard Operation Procedure (SOP).

5. MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:

Please refer to the Monument Butte Field SOP. See Exhibit "C".

6. TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:

Please refer to the Monument Butte Field SOP.

7. AUXILIARY SAFETY EQUIPMENT TO BE USED:

Please refer to the Monument Butte Field SOP.

8. TESTING, LOGGING AND CORING PROGRAMS:

Please refer to the Monument Butte Field SOP.

9. ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:

The anticipated maximum bottom hole pressure is 2000 psi. It is not anticipated that abnormal temperatures will be encountered.

10. ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:

Please refer to the Monument Butte Field SOP.

**INLAND PRODUCTION COMPANY
FEDERAL #11-7-9-18
NE/SW SECTION 7, T9S, R18E
UINTAH COUNTY, UTAH**

ONSHORE ORDER NO. 1

MULTI-POINT SURFACE USE & OPERATIONS PLAN

1. EXISTING ROADS

See attached Topographic Map "A"

To reach Inland Production Company well location site Federal #11-7-9-18 located in the NE 1/4 SW 1/4 Section 7, T9S, R18E, Uintah County, Utah:

Proceed southwesterly out of Myton, Utah along Highway 40 - 1.6 miles \pm to the junction of this highway and UT State Hwy 53; proceed southeasterly along Hwy 53 - 11.7 miles \pm to it's junction with an existing road to the southeast; proceed southeasterly - 3.6 miles \pm to it's junction with an existing road to the east; proceed northeasterly - 0.9 miles \pm to it's junction with the beginning of the proposed access road; proceed northerly along the proposed access road 395' \pm to the proposed well location.

2. PLANNED ACCESS ROAD

See Topographic Map "B" for the location of the proposed access road.

3. LOCATION OF EXISTING WELLS

Refer to Exhibit "B".

4. LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

Please refer to the Monument Butte Field Standard Operating Procedure (SOP).

5. LOCATION AND TYPE OF WATER SUPPLY

Please refer to the Monument Butte Field SOP. See Exhibit "A".

6. SOURCE OF CONSTRUCTION MATERIALS

Please refer to the Monument Butte Field SOP.

7. METHODS FOR HANDLING WASTE DISPOSAL

Please refer to the Monument Butte Field SOP.

8. ANCILLARY FACILITIES

Please refer to the Monument Butte Field SOP.

9. **WELL SITE LAYOUT**

See attached Location Layout Diagram.

10. **PLANS FOR RESTORATION OF SURFACE**

Please refer to the Monument Butte Field SOP.

11. **SURFACE OWNERSHIP** - Bureau Of Land Management

12. **OTHER ADDITIONAL INFORMATION**

The Archaeological Resource Survey and Paleontological Resource Survey for this area are attached. MOAC Report #03-213, 1/20/04. Paleontological Resource Survey prepared by, Wade E. Miller, 11/21/03. See attached report cover pages, Exhibit "D".

Inland Production Company requests a 60' ROW for the Federal #11-7-9-18 to allow for construction of a 6" gas gathering line, and a 3" poly fuel gas line. Both lines will tie in to the existing pipeline infrastructure. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

Inland Production Company also requests a 60' ROW be granted for the Federal #11-7-9-18 to allow for construction of a 3" steel water injection line and a 3" poly water return line. **Refer to Topographic Map "C."** For a ROW plan of development, please refer to the Monument Butte Field SOP.

Water Disposal

Please refer to the Monument Butte Field SOP.

Reserve Pit Liner

Please refer to the Monument Butte Field SOP.

Location and Reserve Pit Reclamation

Please refer to the Monument Butte Field SOP.

The following seed mixture will be used on the topsoil stockpile, the recontoured surface of the reserve pit, and for final reclamation: (All poundages are in pure live seed)

Shadscale	<i>Atriplex confertifolia</i>	4 lbs/acre
Gardners Saltbush	<i>Atriplex corrugata</i>	4 lbs/acre
Galleta Grass	<i>Hilaria jamesii</i>	4 lbs/acre

Details of the On-Site Inspection

The proposed Federal #11-7-9-18 was on-sited on 8/21/03. The following were present; Brad Mecham (Inland Production), Byron Tolman (Bureau of Land Management), and a SWCA representative. Weather conditions were clear.

13. **LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION**

Representative

Name: Brad Mecham

Address: Route #3 Box 3630
Myton, UT 84052

Telephone: (435) 646-3721


Certification

Please be advised that INLAND PRODUCTION COMPANY is considered to be the operator of well #11-7-9-18 NE/SW Section 7, Township 9S, Range 18E: Lease U-16540 Uintah County, Utah: and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4488944.

I hereby certify that the proposed drillsite and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Inland Production Company and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.


1/26/04

Date


Mandie Crozier
Regulatory Specialist

INLAND PRODUCTION COMPANY

FEDERAL 11-7-9-18
Section 7, T9S, R18E, S.L.B.&M.



REFERENCE POINTS

210' NORTH = 5071.2'
260' NORTH = 5071.0'
170' EAST = 5070.7'
220' EAST = 5070.8'

SURVEYED BY: K.G.S.





SCALE: 1" = 50'

DRAWN BY: J.R.S.

DATE: 10-8-03

Tri State
Land Surveying, Inc.
180 NORTH VERNAL AVE. VERNAL, UTAH 84078
(435) 781-2501

INLAND PRODUCTION COMPANY
CROSS SECTIONS
FEDERAL 11-7-9-18



NOTE:
 UNLESS OTHERWISE NOTED
 ALL CUT/FILL SLOPES ARE
 AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)				
ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	440	440	Topsoil is not included in Pad Cut	0
PIT	640	0		640
TOTALS	1,080	440	890	640

SURVEYED BY: K.G.S.

SCALE: 1" = 50'

DRAWN BY: J.R.S.


DATE: 10-8-03

(435) 781-2501

Tri State
Land Surveying, Inc.
 180 NORTH VERNAL AVE. VERNAL, UTAH 84078

PROPOSED ACCESS
ROAD (Max. 6% Grade)





**Federal 11-7-9-18
SEC. 7, T9S, R18E, S.L.B.&M.**




**Tri-State
Land Surveying Inc.**
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

**SCALE: 1 = 120,000
DRAWN BY: R.A.B.
DATE: 10-10-2003**

Legend
— Existing Road
— Proposed Access

TOPOGRAPHIC MAP

"A"



**Federal 11-7-9-18
SEC. 7, T9S, R18E, S.L.B.&M.**




**Tri-State
Land Surveying Inc.**
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: R.A.B.
DATE: 10-10-2003

Legend
— Existing Road
— Proposed Access

TOPOGRAPHIC MAP

"B"



Federal 11-7-9-18
SEC. 7, T9S, R18E, S.L.B.&M.



Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: R.A.B.


DATE: 10-10-2003

Legend

- Roads
- Existing Gas Line
- Proposed Gas Line
- Existing Water Line
- Proposed Water Line

TOPOGRAPHIC MAP

"C"



January 15, 2003

UTU-74404

UTU-79014

UTU-65970

UTU-64806

UTU-74835

UTU-75234

U-39713

U-39714

Proposed Location
Federal 11-7-9-18



Federal 11-7-9-18
SEC. 7, T9S, R18E, S.L.B.&M.



(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: R.A.B.

DATE: 10-10-2003

Legend

- Well Locations
- One-Mile Radius

Exhibit "B"

2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

CULTURAL RESOURCE INVENTORY OF
INLAND PRODUCTION'S BLOCK PARCEL IN
TOWNSHIP 9 SOUTH, RANGE 18 EAST, SECTION 7
IN UINTAH COUNTY, UTAH

by

Katie Simon
and
Keith R. Montgomery

Prepared For:

Bureau of Land Management
Vernal Field Office

Prepared Under Contract With:

Inland Production
Route 3 Box 3630
Myton, Utah 84052

Prepared By:

Montgomery Archaeological Consultants
P.O. Box 147
Moab, Utah 84532

MOAC Report No. 03-213

January 20, 2004

United States Department of Interior (FLPMA)
Permit No. 03-UT-60122

State of Utah Antiquities Project (Survey)
Permit No. U-04-MQ-0006,b

INLAND RESOURCES, INC.

**PALEONTOLOGICAL FIELD SURVEY OF PROPOSED
PRODUCTION DEVELOPMENT AREAS,
UINTAH COUNTY, UTAH**

**ADDENDUM OF SECTION 7, T 9 S, R 18 E
TO REPORT OF:**

**Sections 3, 4, & 10, T 9 S, R 18 E; Section 7,
T 9 S, R 19 E (dated November 15, 2003)**

REPORT OF SURVEY

Prepared for:

Inland resources, Inc.

Prepared by:

Wade E. Miller
Consulting Paleontologist
November 21, 2003

004

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 01/27/2004

API NO. ASSIGNED: 43-047-35451

WELL NAME: FEDERAL 11-7-9-18

OPERATOR: INLAND PRODUCTION (N5160)

CONTACT: MANDIE CROZIER

PHONE NUMBER: 435-646-3721

PROPOSED LOCATION:

NESW 07 090S 180E

SURFACE: 1980 FSL 1977 FWL

BOTTOM: 1980 FSL 1977 FWL

UINTAH

8 MILE FLAT NORTH (590)

LEASE TYPE: 1 - Federal

LEASE NUMBER: U-16540

SURFACE OWNER: 1 - Federal

PROPOSED FORMATION: GRRV

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering		
Geology		
Surface		

LATITUDE: 40.04354

LONGITUDE: 109.93776

RECEIVED AND/OR REVIEWED:

☒ Plat☒ Bond: Fed[1] Ind[] Sta[] Fee[]
(No. 4488944)☒ Potash (Y/N)☒ Oil Shale 190-5 (B) or 190-3 or 190-13☒ Water Permit
(No. MUNICIPAL)☒ RDCC Review (Y/N)
(Date:)☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

R649-2-3.

Unit EIGHT MILE FLAT

☒ R649-3-2. General
Siting: 460 From Qtr/Qtr & 920' Between Wells

R649-3-3. Exception

Drilling Unit

Board Cause No: _____

Eff Date: _____

Siting: _____


R649-3-11. Directional Drill

COMMENTS:

Sup, Separate file

STIPULATIONS:

*1- Federal Approval
2- Spacing Strip*



OPERATOR: INLAND PRODUCTION CO (N5160)

SEC. 7 T.9S, R.18E

FIELD: EIGHT MILE FLAT NORTH (590)

COUNTY: UTAH

SPACING: R649-3-2 / GENERAL SITING

Wells


- GAS INJECTION
- GAS STORAGE
- LOCATION ABANDONED
- NEW LOCATION
- PLUGGED & ABANDONED
- PRODUCING GAS
- PRODUCING OIL
- SHUT-IN GAS
- SHUT-IN OIL
- TEMP. ABANDONED
- TEST WELL
- WATER INJECTION
- WATER SUPPLY
- WATER DISPOSAL

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED



Utah Oil Gas and Mining



PREPARED BY: DIANA WHITNEY
DATE: 28-JANUARY-2004



State of Utah

Department of
Natural Resources

Division of
Oil, Gas & Mining

ROBERT L. MORGAN
Executive Director

LOWELL P. BRAXTON
Division Director

MICHAEL O. LEAVITT
Governor

OLENE S. WALKER
Lieutenant Governor

January 28, 2004

Inland Production Company
Rt. 3, Box 3630
Myton, UT 84052

Re: Federal 11-7-9-18 Well, 1980' FSL, 1977' FWL, NE SW, Sec. 7, T. 9 South,
R. 18 East, Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-35451.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".

John R. Baza
Associate Director

pab
Enclosures

cc: Uintah County Assessor
Bureau of Land Management, Vernal District Office

Operator: Inland Production Company
Well Name & Number Federal 11-7-9-18
API Number: 43-047-35451
Lease: U-16540

Location: NE SW Sec. 7 T. 9 South R. 18 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

Notify the Division within 24 hours of spudding the well.

- Contact Carol Daniels at (801) 538-5284.

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dan Jarvis at (801) 538-5338

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

006

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

5. Lease Designation and Serial No.

UTU-16540

6. If Indian, Allottee or Tribe Name

NA

7. If Unit or CA, Agreement Designation

N/A

8. Well Name and No.

FEDERAL 11-7-9-18

9. API Well No.

43-047-35451

10. Field and Pool, or Exploratory Area

EIGHT MILE FLAT NORTH

11. County or Parish, State

UINTAH COUNTY, UT.

SUBMIT IN TRIPLICATE

1. Type of Well



Oil
Well



Gas
Well



Other

2. Name of Operator

INEWFIELD PRODUCTION COMPANY

3. Address and Telephone No.

Rt. 3 Box 3630, Myton Utah, 84052 435-646-3721

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

1980 FSL 1977 FWL NE/SW Section 7, T9S R18E

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION



Notice of Intent



Subsequent Report



Final Abandonment Notice

TYPE OF ACTION



Abandonment



Recompletion



Plugging Back



Casing Repair



Altering Casing



Other

Permit Extension



Change of Plans



New Construction



Non-Routine Fracturing



Water Shut-Off



Conversion to Injection



Dispose Water

(Note: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Newfield Production Company requests to extend the Permit to Drill this well for one year. The original approval date was 1/28/04 (expiration 1/28/05).

Approved by the
Utah Division of
Oil, Gas and Mining

Date: 01-18-05

By: [Signature]

COPY SENT TO OPERATOR
Date: 1-20-05
Initials: CHD

RECEIVED
JAN 14 2005

DIV. OF OIL, GAS & MINING

14. I hereby certify that the foregoing is true and correct

Signed

[Signature]
Mandie Crozier

Title

Regulatory Specialist

Date

1/12/2005

CC: UTAH DOGM

(This space for Federal or State office use)

Approved by

Title

Date

Conditions of approval, if any:

CC: Utah DOGM

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**Application for Permit to Drill
Request for Permit Extension
Validation**

(this form should accompany the Sundry Notice requesting permit extension)

API: 43-047-35451
Well Name: Federal 11-7-9-18
Location: NE/SW Section 7, T9S R18E
Company Permit Issued to: Newfield Production Company
Date Original Permit Issued: 1/28/2004

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.

If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes ☐ No ☒ NA

Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes ☐ No ☒

Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes ☐ No ☒

Have there been any changes to the access route including ownership, or right-of-way, which could affect the proposed location? Yes ☐ No ☒

Has the approved source of water for drilling changed? Yes ☐ No ☒

Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes ☐ No ☒

Is bonding still in place, which covers this proposed well? Yes ☒ No ☐

Mandi Cruzin
Signature

1/12/2005

Date

Title: Regulatory Specialist

Representing: Newfield Production Company

RECEIVED
JAN 14 2005
OIL, GAS & MINING

007

RECEIVED
JAN 27 2005
BLM VERNAL, UTAH

Form 3160-3
(September 2001)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

FORM APPROVED
OMB No. 1004-0136
Expires January 31, 2004

5. Lease Serial No.

U-16540

6. If Indian, Allottee or Tribe Name

N/A

7. If Unit or CA Agreement, Name and No.

8. Lease Name and Well No.

Federal 11-7-9-18

9. API Well No.

43.047.35451

10. Field and Pool, or Exploratory

Eight Mile Flat

11. Sec., T., R., M., or Blk. and Survey or Area

NE/SW Sec. 7, T9S R18E

12. County or Parish

Uintah

13. State

UT

1a. Type of Work: ☒ DRILL ☐ REENTER

1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

2. Name of Operator

Newfield Production Company

3a. Address

Route #3 Box 3630, Myton UT 84052

3b. Phone No. (include area code)

(435) 646-3721

4. Location of Well (Report location clearly and in accordance with any State requirements.)*

At surface NE/SW 1980' FSL 1977' FWL

At proposed prod. zone

14. Distance in miles and direction from nearest town or post office*

Approximatley 17.8 miles southeast of Myton, Utah

15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) Approx. 1977' f/lse, NA f/unit

16. No. of Acres in lease

1356.44

17. Spacing Unit dedicated to this well

40 Acres

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. Approx. 1977'

19. Proposed Depth

6500'

20. BLM/BIA Bond No. on file

#4400944- UT0056

21. Elevations (Show whether DF, KDB, RT, GL, etc.)

5072' GL

22. Approximate date work will start*

2nd Quarter 2004

23. Estimated duration

Approximately seven (7) days from spud to rig release.

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification.
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature

Mandie Crozier

Name (Printed/Typed)

Mandie Crozier

Title

Regulatory Specialist

Approved by (Signature)

Assistant Field Manager
Mineral Resources

Name (Printed/Typed)

Office

RECEIVED

JAN 31 2005

Date

1/26/04

DIV. OF OIL, GAS & MINING

Date

01/27/2005

Application approval does not warrant or certify the the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*(Instructions on reverse)

NOTICE OF APPROVAL

UDOGM

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Newfield Production Company
Well Name & Number: Federal 11-7-9-18
API Number: 43-047-35451
Lease Number: U-16540
Location: NESW Sec. 7 T. 9S R. 18E
Agreement: N/A

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

**Please submit to this office, in LAS format, an electronic copy of all logs run on this well
This submission will replace the requirement for submittal of paper logs to the BLM.**

In the event after-hours approvals are necessary, you must contact one of the following individuals:

Ed Forsman (435) 828-7874
Petroleum Engineer

Kirk Fleetwood (435) 828-7875
Petroleum Engineer

BLM FAX Machine (435) 781-4410

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

No construction or drilling shall be allowed during the burrowing owl nesting season (April 1 to Aug. 15), without first consulting the BLM biologist. If no nesting owls are found, drilling will be allowed.

Mountain Plover surveys will have to be conducted in accordance with the U.S. Fish and Wildlife Service Mountain Plover Survey Guidelines.

To reduce noise levels in the area, a hospital muffler or multi-cylinder engine shall be installed on the pumping unit.



Office of the Secretary of State


The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
INLAND PRODUCTION COMPANY

FILED
In the Office of the
Secretary of State of Texas
SEP 02 2004
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs
Susan G. Riggs, Treasurer



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155
<http://www.blm.gov>



IN REPLY REFER TO:
3106
(UT-924)

September 16, 2004

Memorandum

To: Vernal Field Office
From: Acting Chief, Branch of Fluid Minerals
Subject: Merger Approval

Attached is an approved copy of the name change recognized by the Utah State Office. We have updated our records to reflect the merger from Inland Production Company into Newfield Production Company on September 2, 2004.

Michael Coulthard
Acting Chief, Branch of
Fluid Minerals

Enclosure

1. State of Texas Certificate of Registration

cc: MMS, Reference Data Branch, James Sykes, PO Box 25165, Denver CO 80225
State of Utah, DOGM, Attn: Earlene Russell, PO Box 145801, SLC UT 84114
Teresa Thompson
Joe Incardine
Connie Seare

UTSL-	15855	61052	73088	76561	
071572A	16535	62848	73089	76787	
065914	16539	63073B	73520A	76808	
	16544	63073D	74108	76813	
	17036	63073E	74805	76954	63073X
	17424	63073O	74806	76956	63098A
	18048	64917	74807	77233	68528A
UTU-	18399	64379	74808	77234	72086A
	19267	64380	74389	77235	72613A
02458	26026A	64381	74390	77337	73520X
03563	30096	64805	74391	77338	74477X
03563A	30103	64806	74392	77339	75023X
04493	31260	64917	74393	77357	76189X
05843	33992	65207	74398	77359	76331X
07978	34173	65210	74399	77365	76788X
09803	34346	65635	74400	77369	77098X
017439B	36442	65967	74404	77370	77107X
017985	36846	65969	74405	77546	77236X
017991	38411	65970	74406	77553	77376X
017992	38428	66184	74411	77554	78560X
018073	38429	66185	74805	78022	79485X
019222	38431	66191	74806	79013	79641X
020252	39713	67168	74826	79014	80207X
020252A	39714	67170	74827	79015	81307X
020254	40026	67208	74835	79016	
020255	40652	67549	74868	79017	
020309D	40894	67586	74869	79831	
022684A	41377	67845	74870	79832	
027345	44210	68105	74872	79833	
034217A	44426	68548	74970	79831	
035521	44430	68618	75036	79834	
035521A	45431	69060	75037	80450	
038797	47171	69061	75038	80915	
058149	49092	69744	75039	81000	
063597A	49430	70821	75075		
075174	49950	72103	75078		
096547	50376	72104	75089		
096550	50385	72105	75090		
	50376	72106	75234		
	50750	72107	75238		
10760	51081	72108	76239		
11385	52013	73086	76240		
13905	52018	73087	76241		
15392	58546	73807	76560		

OPERATOR CHANGE WORKSHEET

008

ROUTING

1. GLH

2. CDW

3. FILE

Change of Operator (Well Sold)

Designation of Agent/Operator

X Operator Name Change

Merger

The operator of the well(s) listed below has changed, effective:

9/1/2004

FROM: (Old Operator):

N5160-Inland Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

TO: (New Operator):

N2695-Newfield Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

CA No.

Unit:

WELL(S)

NAME	SEC	TWN	RNG	API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	
FEDERAL 13-1-9-17	01	090S	170E	4304735181	14101	Federal	OW	P	K
FEDERAL 15-1-9-17	01	090S	170E	4304735182	14094	Federal	OW	P	K
FEDERAL 3-11-9-17	11	090S	170E	4304735295	14258	Federal	OW	P	K
FEDERAL 5-5-9-18	05	090S	180E	4304735290		Federal	OW	NEW	K
FEDERAL 7-5-9-18	05	090S	180E	4304735291		Federal	OW	APD	K
FEDERAL 9-5-9-18	05	090S	180E	4304735292	14554	Federal	OW	DRL	K
FEDERAL 11-5-9-18	05	090S	180E	4304735293		Federal	OW	APD	K
FEDERAL 13-5-9-18	05	090S	180E	4304735294		Federal	OW	APD	K
FEDERAL 9-6-9-18	06	090S	180E	4304735183	14153	Federal	OW	P	K
FEDERAL 11-6-9-18	06	090S	180E	4304735184	14127	Federal	OW	P	K
FEDERAL 15-6-9-18	06	090S	180E	4304735185	14120	Federal	OW	P	K
FEDERAL 1-6-9-18	06	090S	180E	4304735296		Federal	OW	NEW	K
FEDERAL 1-7-9-18	07	090S	180E	4304735447		Federal	OW	APD	K
FEDERAL 3-7-9-18	07	090S	180E	4304735448		Federal	OW	APD	K
FEDERAL 5-7-9-18	07	090S	180E	4304735449		Federal	OW	APD	K
FEDERAL 7-7-9-18	07	090S	180E	4304735450		Federal	OW	APD	K
FEDERAL 11-7-9-18	07	090S	180E	4304735451		Federal	OW	APD	K
FEDERAL 13-7-9-18	07	090S	180E	4304735452		Federal	OW	APD	K
FEDERAL 10-7-9-18	07	090S	180E	4304735453		Federal	OW	APD	K
FEDERAL 14-7-9-18	07	090S	180E	4304735454		Federal	OW	APD	K

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/15/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/15/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/23/20054. Is the new operator registered in the State of Utah: YES Business Number: 755627-01435. If **NO**, the operator was contacted on:

- 6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 2/28/2005
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The NEW operator of any fee well(s) listed covered by Bond Number 61BSBDH2919
2. The FORMER operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The FORMER operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

Name of Company: NEWFIELD PRODUCTION COMPANY

Well Name: FEDERAL 11-7-9-18

Api No: 43-047-35451 Lease Type: FEDERAL

Section 07 Township 09S Range 18E County UINTAH

Drilling Contractor NDSI RIG # NS#1

SPUDDED:

Date 06/08/05

Time 1:30 PM

How DRY

Drilling will Commence: _____

Reported by FLOYD MITCHELL

Telephone # 1-435-823-3610

Date 06/08/2005 Signed CHD

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR: NEWFIELD PRODUCTION COMPANY
ADDRESS: RT. 3 BOX 3690
MYTON, UT 84052


OPERATOR ACCT. NO. N2006

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	14767	43-047-35454	Federal 14-7-9-18	SE/SW	7	9S	18E	Utah	6/07/2005	
WELL 1 COMMENTS: <u>GRPV</u>											
A	99999	14768	43-047-35451	Federal 11-7-9-18	NE/SW	7	9S	16E	Utah	6/08/2005	
WELL 2 COMMENTS: <u>GRPV</u>											
A	99999	14769	43-047-35293	Federal 11-5-9-18	NE/SW	5	9S	16E	Utah	6/10/2005	
WELL 3 COMMENTS: <u>GRPV</u>											
A	99999	14770	43-047-36068	Federal 14-14-9-17	SE/SW	14	9S	17E	Utah	6/13/2005	
WELL 4 COMMENTS: <u>GRPV</u>											
WELL 5 COMMENTS:											

ACTION CODES (See instruction on back of form)

- A - Establish new entity for new well (single well only)
- E - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other - explain in comments section

NOTE: Use COMMENT section to explain why each Action Code was selected.


Signature Kobbie S. Jones
Production Clerk
Date June 13, 2005

RECEIVED

JUN 13 2005

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

5. Lease Serial No.
UTU16540

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.
FEDERAL 11-7-9-18

9. API Well No.
4304735451

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State
Uintah, UT

1. Type of Well
☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator
Newfield Production Company

3a. Address Route 3 Box 3630
Myton, UT 84052

3b. Phone No. (include are code)
435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
1980 FSL 1977 FWL
NE/SW Section 7 T9S R18E

12. CHECK APPROPRIATE BOX(ES) TO INIDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Spud Notice
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 6-08-05 MIRU NDSI spud rig #1. Drill 310' of 12 1/4" hole with air mist. TIH W/7 Jt's 8 5/8" J-55 24# csgn. Set @ 317.09'KB. On 6-10-05 Cement with 160 sks of Class "G" w/ 2% CaCL+ 1/4# Cello Flake. Mixed @ 15.8 ppg> 1.17 cf/sk yeild. Returned 4 bbls cement to pit.

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)
Ray Herrera

Title

Drilling Foreman

Signature

Ray Herrera

Date

06/13/2005

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

RECEIVED

JUN 20 2005

BUREAU OF LAND MANAGEMENT

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8 CASING SET AT 317.09

LAST CASING 8 5/8" SET AT 317.09'
 DATUM 12' KB
 DATUM TO CUT OFF CASING _____
 DATUM TO BRADENHEAD FLANGE _____
 TD DRILLER 310' LOGGER _____
 HOLE SIZE 12 1/4

OPERATOR Newfield Production Company
 WELL Federal 11-7-9-18
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # NDSI NS #1

LOG OF CASING STRING:

LOG OF CASING STRING.								
PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH	
		Shoe Joint 43.55'						
		WHI - 92 csg head			8rd	A	0.95	
7	8 5/8"	Maverick ST&C csg	24#	J-55	8rd	A	305.24	
		GUIDE shoe			8rd	A	0.9	
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING				307.09
TOTAL LENGTH OF STRING		307.09	7	LESS CUT OFF PIECE				2
LESS NON CSG. ITEMS		1.85		PLUS DATUM TO T/CUT OFF CSG				12
PLUS FULL JTS. LEFT OUT		0		CASING SET DEPTH				317.09
TOTAL		305.24	7	} COMPARE				
TOTAL CSG. DEL. (W/O THRDS)		302.66	7					
TIMING		1ST STAGE						
BEGIN RUN CSG.		Spud	6/8/2005	1:30 PM	GOOD CIRC THRU JOB		Yes	
CSG. IN HOLE			6/8/2005	3:00 PM	Bbls CMT CIRC TO SURFACE		4 bbls	
BEGIN CIRC			6/10/2005	8:10 AM	RECIPROCATED PIPE FOR		N/A	
BEGIN PUMP CMT			6/10/2005	8:21 AM				
BEGIN DSPL. CMT			6/10/2005	8:31 AM	BUMPED PLUG TO		747	PSI
PLUG DOWN			6/10/2005	8:36 AM				
CEMENT USED		CEMENT COMPANY- B. J.						
STAGE	# SX	CEMENT TYPE & ADDITIVES						
1	160	Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield						
CENTRALIZER & SCRATCHER PLACEMENT			SHOW MAKE & SPACING					
Centralizers - Middle first, top second & third for 3								

COMPANY REPRESENTATIVE Ray Herrera

RECEIVED

DATE 6/10/2005

JUN 20 2005

DIV. OF OIL, GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1980 FSL 1977 FWL

NE/SW Section 7 T9S R18E

5. Lease Serial No.

UTU16540

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

8. Well Name and No.

FEDERAL 11-7-9-18

9. API Well No.

4304735451

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Weekly Status Report
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

On 6/18/2005 MIRU Patterson Rig # 155. Set all equipment. Pressure test Kelly, TIW, Choke manifold, & Bop's to 2,000 psi. Test 8.625 csgn to 1,500 psi. Vernal BLM field, & Roosevelt DOGM office was notified of test. PU BHA and tag cement @ 263'. Drill out cement & shoe. Drill a 7.875 hole with fresh water to a depth of 5865'. Lay down drill string & BHA. Open hole log w/ Dig/SP/GR log's TD to surface. PU & TIH with Guide shoe, shoe jt, float collar, 137 jt's of 5.5 J-55, 15.5# csgn. Set @ 5842.69' / KB. Cement with 350sks cement mixed @ 11.0 ppg & 3.43 yld. The 450 sks cement mixed @ 14.4 ppg & 1.24 yld. With 8 bbls returned to pit. Nipple down Bop's. Drop slips @ 83,000 #'s tension. Release rig 7:30 PM on 6/22/2005.

I hereby certify that the foregoing is true and correct

Name (Printed/ Typed)
Floyd Mitchell

Signature *Floyd Mitchell*

Title

Drilling Supervisor

Date

06/23/2005

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

RECEIVED

JUN 29 2005

DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY - CASING & CEMENT REPORT

5 1/2" CASING SET AT 5842.69

Flt cllr @ 5800'

LAST CASING 8 5/8" SET AT 317'

OPERATOR Inland Production Company

DATUM 12' KB

WELL Federal 11-7-9-18

DATUM TO CUT OFF CASING 12'

FIELD/PROSPECT Monument Butte

DATUM TO BRADENHEAD FLANGE

CONTRACTOR & RIG # Patterson- Rig # 155

TD DRILLER 5865' Loggers TD 5851'

HOLE SIZE 7 7/8"

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		Landing Jt					14
	SHJT	5.60' @ 3966'					
137	5 1/2"	ETC LT & C casing	15.5#	J-55	8rd	A	5786.99
		Float collar					0.6
1	5 1/2"	ETC LT&C csg	15.5#	J-55	8rd	A	42.45
		GUIDE shoe			8rd	A	0.65
CASING INVENTORY BAL.		FEET	JTS	TOTAL LENGTH OF STRING			5844.69
TOTAL LENGTH OF STRING		5844.69	138	LESS CUT OFF PIECE			14
LESS NON CSG. ITEMS		15.25		PLUS DATUM TO T/CUT OFF CSG			12
PLUS FULL JTS. LEFT OUT		127.67	3	CASING SET DEPTH			5842.69
TOTAL		5957.11	141	} COMPARE			
TOTAL CSG. DEL. (W/O THRDS)		5957.11	141				
TIMING		1ST STAGE	2nd STAGE				
BEGIN RUN CSG.		6/22/2005	8:00 AM	GOOD CIRC THRU JOB <u>Yes</u>			
CSG. IN HOLE		6/22/2005	11:00 AM	Bbls CMT CIRC TO SURFACE <u>8</u>			
BEGIN CIRC		6/22/2005	11:00 AM	RECIPROCATED PIPE FOR <u>THRUSTROKE</u>			
BEGIN PUMP CMT		6/22/2005	1:24 PM	DID BACK PRES. VALVE HOLD ? <u>Yes</u>			
BEGIN DSPL. CMT		6/22/2005	2:12 PM	BUMPED PLUG TO <u>2049</u> PSI			
PLUG DOWN		6/22/2005	2:40 PM				

CEMENT USED		4 CEMENT COMPANY- B. J.	
STAGE	# SX	CEMENT TYPE & ADDITIVES	
1	350	Premlite II w/ 10% gel + 3 % KCL, 3#s /sk CSE + 2# sk/kolseal + 1/2#s/sk Cello Flake	
		mixed @ 11.0 ppg W / 3.43 cf/sk yield	
2	450	50/50 poz W/ 2% Gel + 3% KCL, .5%EC1,1/4# sk C.F. 2% gel. 3% SM mixed @ 14.4 ppg W/ 1.24 YLD	
CENTRALIZER & SCRATCHER PLACEMENT :		SHOW MAKE & SPACING	
Centralizers - Middle first, top second & third. Then every third collar for a total of 20.			

COMPANY REPRESENTATIVE Floyd Mitchell

DATE 6/23/2005



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155



IN REPLY REFER TO
3180
UT-922

June 30, 2005

Newfield Production Company
Attn: Kelly L. Donohoue
1401 Seventeenth Street, Suite 1000
Denver, Colorado 80202

Gentlemen:

The Sundance (Green River) Unit Agreement, Uintah County, Utah, was approved June 30, 2005. This agreement has been designated No. UTU82472X, and is effective July 1, 2005. The unit area embraces 11,143.86 acres, more or less.

Pursuant to regulations issued and effective June 17, 1988, all operations within the Sundance (Green River) Unit will be covered by your nationwide (Utah) oil and gas bond No. 0056.

The following leases embrace lands included within the unit area:

UTU0075174	UTU39713	UTU65970*	UTU79013*
UTU16539*	UTU39714	UTU74404	UTU79014*
UTU16540	UTU44429	UTU74835	UTU80915
UTU17424*	UTU64806*	UTU74872*	UTU82205
UTU18043	UTU65969	UTU75234	

* Indicates lease to be considered for segregation by the Bureau of Land Management pursuant to Section 18 (g) of the unit agreement and Public Law 86-705.

All lands and interests by State of Utah, Cause No. 228-08 are fully committed.

Approval of this agreement does not warrant or certify that the operator thereof and other holders of operating rights hold legal or equitable title to those rights in the subject leases which are committed hereto.

RECEIVED

JUL 8 / 2005

DIV. OF OIL, GAS & MINING

*Docket No
2005-009*

We are of the opinion that the agreement is necessary and advisable in the public interest and for the purpose of more properly conserving natural resources. Certification-Determination, signed by the School and Institutional Trust Land Administration for the State of Utah, is attached to the enclosed agreement. We request that you furnish the State of Utah and all other interested principals with appropriate evidence of this approval.

Sincerely,

/s/ Terry Catlin

Terry Catlin
Acting Chief, Branch of Fluid Minerals

Enclosure

bcc: Mary Higgins w/enclosure
MMS - Data Management Division (Attn: James Sykes)
Trust Lands Administration
Division of Oil, Gas and Mining
Field Manager - Vernal w/enclosure
File - Sundance (Green River) Unit w/enclosure
Agr. Sec. Chron
Fluid Chron
Central Files

UT922:TAThompson:tt:06/30/2005

Entity Form 6
"C" Change from one existing entity to another existing entity

API	Well	Sec	Twsp	Rng	Entity	Entity Eff Date
4304734937	FEDERAL 14-6-9-18	06	090S	180E	14064 to 14844	9/20/2005
4304735183	FEDERAL 9-6-9-18	06	090S	180E	14153 to 14844	9/20/2005
4304735184	FEDERAL 11-6-9-18	06	090S	180E	14127 to 14844	9/20/2005
4304735185	FEDERAL 15-6-9-18	06	090S	180E	14120 to 14844	9/20/2005
4304735751	FEDERAL 16-6-9-18	06	090S	180E	14623 to 14844	9/20/2005
4304735752	FEDERAL 12-6-9-18	06	090S	180E	14649 to 14844	9/20/2005
4304735753	FEDERAL 10-6-9-18	06	090S	180E	14622 to 14844	9/20/2005
4304731126	FEDERAL 6-7-9-18	07	090S	180E	14599 to 14844	9/20/2005
4304731202	FEDERAL 15-7-9-18	07	090S	180E	564 to 14844	9/20/2005
4304735448	FEDERAL 3-7-9-18	07	090S	180E	14661 to 14844	9/20/2005
4304735449	FEDERAL 5-7-9-18	07	090S	180E	14662 to 14844	9/20/2005
4304735451	FEDERAL 11-7-9-18	07	090S	180E	14768 to 14844	9/20/2005
4304735452	FEDERAL 13-7-9-18	07	090S	180E	14755 to 14844	9/20/2005
4304735454	FEDERAL 14-7-9-18	07	090S	180E	14767 to 14844	9/20/2005
4304735503	FEDERAL 12-7-9-18	07	090S	180E	14663 to 14844	9/20/2005
4304731274	FEDERAL 7-8-9-18	08	090S	180E	554 to 14844	9/20/2005
4304731545	FEDERAL 4-8-9-18	08	090S	180E	10275 to 14844	9/20/2005
4304731546	FEDERAL 12-8-9-18	08	090S	180E	10975 to 14844	9/20/2005
4304731547	FEDERAL 15-8-9-18	08	090S	180E	10972 to 14844	9/20/2005
4304735811	STATE 1-16-9-18	16	090S	180E	14390 to 14844	9/20/2005
4304735813	STATE 3-16-9-18	16	090S	180E	14565 to 14844	9/20/2005
4304735819	STATE 9-16-9-18	16	090S	180E	14566 to 14844	9/20/2005
4304735822	STATE 11-16-9-18	16	090S	180E	14577 to 14844	9/20/2005
4304731142	FEDERAL 4-18-9-18	18	090S	180E	14600 to 14844	9/20/2005

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1980 FSL 1977 FWL

NE/SW Section 7 T9S R18E

5. Lease Serial No.

UTU16540

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

SUNDANCE UNIT

8. Well Name and No.

FEDERAL 11-7-9-18

9. API Well No.

4304735451

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input checked="" type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Formation water is produced to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Newfield's secondary recovery project.

Water not meeting quality criteria, is disposed at Newfield's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RECEIVED
JUL 21 2005

DIV. OF OIL, GAS & MINING

I hereby certify that the foregoing is true and correct

Name (Printed/Typed)
Mandie Crozier

Title

Regulatory Specialist

Signature

Date

07/18/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0135
Expires January 31, 2004

SUNDRY NOTICES AND REPORTS ON WELLS
Do not use this form for proposals to drill or to re-enter an
abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE - Other Instructions on reverse side

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

Newfield Production Company

3a. Address Route 3 Box 3630

Myton, UT 84052

3b. Phone No. (include area code)

435.646.3721

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1980 FSL 1977 FWL

NE/SW Section 7 T9S R18E

5. Lease Serial No.

UTU16540

6. If Indian, Allottee or Tribe Name.

7. If Unit or CA/Agreement, Name and/or No.

SUNDANCE UNIT

8. Well Name and No.

FEDERAL 11-7-9-18

9. API Well No.

4304735451

10. Field and Pool, or Exploratory Area
Monument Butte

11. County or Parish, State

Uintah, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production(Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other _____
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug & Abandon	<input type="checkbox"/> Temporarily Abandon	Variance _____
	<input type="checkbox"/> Convert to Injector	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	_____

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleate horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

Newfield Production Company is requesting a variance from Onshore Order 43 CFR Part 3160 Section 4 requiring production tanks to be equipped with Enardo or equivalent vent line valves. Newfield operates wells that produce from the Green River formation, which are relatively low gas producers (20 mcfpd). The majority of the wells are equipped with a three phase separator to maximize gas separation and sales.

Newfield is requesting a variance for safety reasons. Crude oil production tanks equipped with back pressure devices will emit a surge of gas when the thief hatches are open. While gauging tanks, lease operators will be subject to breathing toxic gases as well as risk a fire hazard, under optimum conditions

Accepted by the
Utah Division of
Oil, Gas and Mining

Federal Approval Of This
Action Is Necessary

RECEIVED

JUL 21 2005

DIV. OF OIL, GAS & MINING

COPIES SENT TO OPERATOR

DATE: 7-22-05

INITIALS: CHD

Date: 7/21/05
By: [Signature]

I hereby certify that the foregoing is true and correct

Name (Printed/Typed)
Mandie Crozier

Signature

Title

Regulatory Specialist

Date

07/18/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious and fraudulent statements or representations as to any matter within its jurisdiction

(Instructions on reverse)

RECEIVED
AUG 23 2005UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
OIL, GAS & MININGSUBMIT IN DUPLICATE*
(See other instructions on reverse side)FORM APPROVED
OMB NO. 1004-0137
Expires: February 28, 1995

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WORK OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> Other _____		5. LEASE DESIGNATION AND SERIAL NO. UTU-16540	
1b. TYPE OF WELL NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEPEN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF RESVR. <input type="checkbox"/> Other _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME NA	
2. NAME OF OPERATOR Newfield Exploration Company		7. UNIT AGREEMENT NAME Sundance Unit	
3. ADDRESS AND TELEPHONE NO. 1401 17th St. Suite 1000 Denver, CO 80202		8. FARM OR LEASE NAME, WELL NO. Federal 11-7-9-18	
4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.)* At Surface 1980' FSL & 1977' FWL (NE/SW) Sec. 7, T9S, R18E At top prod. Interval reported below		9. WELL NO. 43-047-35451	
At total depth		10. FIELD AND POOL OR WILDCAT Monument Butte	
14. API NO. 43-047-35451		DATE ISSUED 1/28/04	
15. DATE SPUDDED 6/8/05		12. COUNTY OR PARISH Utah	
16. DATE T.D. REACHED 6/22/05		13. STATE UT	
17. DATE COMPL. (Ready to prod.) 7/15/05		11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA Sec. 7, T9S, R18E	
18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* 5072' GL		19. ELEV. CASINGHEAD 5084' KB	
20. TOTAL DEPTH, MD & TVD 5865'		21. PLUG BACK T.D., MD & TVD 5799'	
22. IF MULTIPLE COMPL., HOW MANY*		23. INTERVALS DRILLED BY ----->	
24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)* Green River 4801'-5590'		ROTARY TOOLS X	
25. WAS DIRECTIONAL SURVEY MADE No		CABLE TOOLS	
26. TYPE ELECTRIC AND OTHER LOGS RUN Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log		27. WAS WELL CORED No	
23. CASING RECORD (Report all strings set in well)			
CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE
8-5/8" - J-55	24#	317'	12-1/4"
5-1/2" - J-55	15.5#	5843'	7-7/8"
29. LINER RECORD			
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*
			SCREEN (MD)
			2-7/8"
30. TUBING RECORD			
SIZE	DEPTH SET (MD)	PACKER SET (MD)	
	EOT @	TA @	
	5647'	5549'	
31. PERFORATION RECORD (Interval, size and number)			
INTERVAL	SIZE	SPF/NUMBER	DEPTH INTERVAL (MD)
(CP3) 5566'-5590'	.41"	4/96	5566'-5590'
(CP1&2) 5387'-5400', 5456'-5467'	.41"	4/96	5387'-5467'
(A1&3) 5004'-5020', 5040'-5047'	.41"	4/92	5004'-5047'
(B1) 4801'-4809'	.41"	4/32	4801'-4809'
32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.			
AMOUNT AND KIND OF MATERIAL USED		Frac w/ 60,749# 20/40 sand in 495 bbls fluid	
Frac w/ 69,628# 20/40 sand in 550 bbls fluid		Frac w/ 120,297# 20/40 sand in 844 bbls fluid	
Frac w/ 24,544# 20/40 sand in 273 bbls fluid			
33.* PRODUCTION			
DATE FIRST PRODUCTION 7/15/05	PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump) 2-1/2" x 1-1/2" x 14' RHAC SM Plunger Pump		WELL STATUS (Producing or shut-in) PRODUCING
DATE OF TEST 10 day ave	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD
			----->
FLOW, TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL-BBL. GAS-MCF. WATER-BBL. GAS-OIL RATIO
			63 4 41 63
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Sold & Used for Fuel			
35. LIST OF ATTACHMENTS			
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records			
SIGNED Mandie Crozier		TITLE Regulatory Specialist	
DATE 8/18/2005		MC	

*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
			Well Name Federal 11-7-9-18	Garden Gulch Mkr	3594'	
				Garden Gulch 1	3765'	
				Garden Gulch 2	3877'	
				Point 3 Mkr	4121'	
				X Mkr	4374'	
				Y-Mkr	4409'	
				Douglas Creek Mkr	4542'	
				BiCarbonate Mkr	4771'	
				B Limestone Mkr	4896'	
				Castle Peak	5343'	
				Basal Carbonate	5755'	
				Total Depth (LOGGERS)	5851'	



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY

REGION 8
1595 WYNKOOP STREET
DENVER, CO 80202-1129
<http://www.epa.gov/region8>

JUL 23 2008

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Eric Sundberg
Newfield Production Company
1001 Seventeenth Street, Suite 2000
Denver, CO 80202

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RECEIVED
JUL 28 2008
DIV. OF OIL, GAS & MINING

Re: FINAL Permit
EPA UIC Permit UT21092-07351
Well: Federal 11-7-9-18
Uintah County, UT
API #43-047-35451

95 18E 7

Dear Mr. Sundberg:

Enclosed is your copy of the FINAL Underground Injection Control (UIC) Permit for the proposed Federal 11-7-9-18 injection well. A Statement of Basis that discusses the conditions and requirements of this EPA UIC Permit, is also included.

The Public Comment period for this Permit ended on JUL 18 2008. No comments on the Draft Permit were received during the Public Notice period; therefore the Effective Date for this EPA UIC Permit is the date of issuance. All conditions set forth herein refer to Title 40 Parts 124, 144, 146, and 147 of the Code of Federal Regulations (CFR) and are regulations that are in effect as of the Effective Date of this Permit.

Please note that under the terms and conditions of this Final Permit you are authorized only to construct the proposed injection well. Prior to commencing injection, you first must fulfill all "Prior to Commencing Injection" requirements of the Final Permit, Part II Section C Subpart 1, and obtain written Authorization to Inject from the EPA. It is your responsibility to be familiar with and to comply with all provisions of your Final Permit.


This EPA UIC Permit is issued for the operating life of the well unless terminated (Part III, Section B). The EPA may review this Permit at least every five (5) years to determine whether any action is warranted pursuant to 40 CFR § 144.36(a).



Printed on Recycled Paper

If you have any questions on the enclosed Final Permit or Statement of Basis, please call Bruce Suchomel of my staff at (303) 312-6001, or toll-free at (800) 227-8917, ext. 312-6001.

Sincerely,



Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

enclosure: Final UIC Permit
Statement of Basis
Form 7520-7 Application to Transfer Permit
Form 7520-11 Monitoring Report
Form 7520-13 Plugging Record
Form 7520-12 Well Rework Record

cc: Letter Only:

Curtis Cesspooch, Chairman
Uintah & Ouray Business Committee
Ute Indian Tribe

Irene Cuch, Vice-Chairwoman
Uintah & Ouray Business Committee
Ute Indian Tribe

Ronald Groves, Councilman
Uintah & Ouray Business Committee
Ute Indian Tribe

Steven Cesspooch, Councilman
Uintah & Ouray Business Committee
Ute Indian Tribe

Phillip Chimburas, Councilman
Uintah & Ouray Business Committee
Ute Indian Tribe



Frances Poowegup, Councilwoman
Uintah & Ouray Business Committee
Ute Indian Tribe

Chester Mills, Superintendent
U.S. Bureau of Indian Affairs
Uintah & Ouray Indian Agency

All enclosures:

Michael Guinn, District Manager
Newfield Production Company
Myton, UT

Shaun Chapoose, Director
Land Use Department
Ute Indian Tribe

Larry Love, Director
Energy and Minerals Department
Ute Indian Tribe

Elaine Willie, GAP Coordinator
Land Use Department
Ute Indian Tribe

Gilbert Hunt
Associate Director
Utah Division of Oil, Gas, and Mining

Fluid Minerals Engineering Office
U.S. Bureau of Land Management
Vernal, UT



**UNDERGROUND INJECTION CONTROL PROGRAM
PERMIT**

PREPARED: March 2008

Permit No. UT21092-07351

Class II Enhanced Oil Recovery Injection Well

**Federal 11-7-9-18
Uintah County, UT**

Issued To

Newfield Production Company

1001 Seventeenth Street, Suite 2000

Denver, CO 80202

PART I. AUTHORIZATION TO CONSTRUCT AND OPERATE	2
PART II. SPECIFIC PERMIT CONDITIONS	3
Section A. WELL CONSTRUCTION REQUIREMENTS	3
1. Casing and Cement	3
2. Injection Tubing and Packer	3
3. Sampling and Monitoring Devices	3
4. Well Logging and Testing	4
5. Postponement of Construction or Conversion	4
6. Workovers and Alterations	4
Section B. MECHANICAL INTEGRITY	4
1. Demonstration of Mechanical Integrity (MI)	5
2. Mechanical Integrity Test Methods and Criteria	5
3. Notification Prior to Testing	5
4. Loss of Mechanical Integrity	5
Section C. WELL OPERATION	6
1. Requirements Prior to Commencing Injection	6
2. Injection Interval	6
3. Injection Pressure Limitation	6
4. Injection Volume Limitation	7
5. Injection Fluid Limitation	7
6. Tubing-Casing Annulus (TCA)	7
Section D. MONITORING, RECORDKEEPING, AND REPORTING OF RESULTS	7
1. Monitoring Parameters, Frequency, Records and Reports	7
2. Monitoring Methods	7
3. Records Retention	8
4. Annual Reports	8
Section E. PLUGGING AND ABANDONMENT	8
1. Notification of Well Abandonment, Conversion or Closure	9
2. Well Plugging Requirements	9
3. Approved Plugging and Abandonment Plan	9
4. Forty Five (45) Day Notice of Plugging and Abandonment	9
5. Plugging and Abandonment Report	9
6. Inactive Wells	9

PART III. CONDITIONS APPLICABLE TO ALL PERMITS	11
Section A. EFFECT OF PERMIT	11
Section B. CHANGES TO PERMIT CONDITIONS	11
1. Modification, Reissuance, or Termination	11
2. Conversions	11
3. Transfer of Permit	11
4. Permittee Change of Address	12
5. Construction Changes, Workovers, Logging and Testing Data	12
Section C. SEVERABILITY	12
Section D. CONFIDENTIALITY	12
Section E. GENERAL PERMIT REQUIREMENTS	12
1. Duty to Comply	12
2. Duty to Reapply	13
3. Need to Halt or Reduce Activity Not a Defense	13
4. Duty to Mitigate	13
5. Proper Operation and Maintenance	13
6. Permit Actions	13
7. Property Rights	13
8. Duty to Provide Information	13
9. Inspection and Entry	13
10. Signatory Requirements	14
11. Reporting requirements	14
Section F. FINANCIAL RESPONSIBILITY	15
1. Method of Providing Financial Responsibility	15
2. Insolvency	15
 APPENDIX A - WELL CONSTRUCTION REQUIREMENTS	 A-1
APPENDIX B - LOGGING AND TESTING REQUIREMENTS	B-1
APPENDIX C - OPERATING REQUIREMENTS	C-1
APPENDIX D - MONITORING AND REPORTING REQUIREMENTS	D-1
APPENDIX E - PLUGGING AND ABANDONMENT REQUIREMENTS	E-1
APPENDIX F - CORRECTIVE ACTION REQUIREMENTS	F-1

Part I. AUTHORIZATION TO CONSTRUCT AND OPERATE

Under the authority of the Safe Drinking Water Act and Underground Injection Control (UIC) Program regulations of the U. S. Environmental Protection Agency (EPA) codified at Title 40 of the Code of Federal Regulations (40 CFR) Parts 2, 124, 144, 146, and 147, and according to the terms of this Permit,

Newfield Production Company
1001 Seventeenth Street, Suite 2000
Denver, CO 80202

is authorized to construct and to operate the following Class II injection well or wells:

Federal 11-7-9-18
1980' FSL & 1977' FWL, NESW S7, T9S, R18E
Uintah County, UT


EPA regulates the injection of fluids into injection wells so that injection does not endanger underground sources of drinking water (USDWs). EPA UIC Permit conditions are based on authorities set forth at 40 CFR Parts 144 and 146, and address potential impacts to USDWs.

Under 40 CFR Part 144, Subpart D, certain conditions apply to all UIC Permits and may be incorporated either expressly or by reference. General permit conditions for which the content is mandatory and not subject to site-specific differences are not discussed in this document. Issuance of this Permit does not convey any property rights of any sort or any exclusive privilege, nor does it authorize injury to persons or property or invasion of other private rights, or any infringement of other Federal, State or local laws or regulations. (40 CFR §144.35) An EPA UIC Permit may be issued for the operating life of the injection well or project unless terminated for reasonable cause under 40 CFR §§144.39, 144.40 and 144.41, and may be reviewed at least once every five (5) years to determine if action is required under 40 CFR §144.36(a).

This Permit is issued for the life of the well(s) unless modified, revoked and reissued, or terminated under 40 CFR 144.39 or 144.40. This EPA Permit may be adopted, modified, revoked and reissued, or terminated if primary enforcement authority for a UIC Program is delegated to an Indian Tribe or State. Upon the effective date of delegation, reports, notifications, questions and other correspondence should be directed to the Indian Tribe or State Director.

Issue Date: JUL 18 2008

Effective Date JUL 23 2008


for Stephen S. Tuber
Assistant Regional Administrator*
Office of Partnerships and Regulatory Assistance

*NOTE: The person holding this title is referred to as the "Director" throughout this Permit.

PART II. SPECIFIC PERMIT CONDITIONS

Section A. WELL CONSTRUCTION REQUIREMENTS

These requirements represent the approved minimum construction standards for well casing and cement, injection tubing, and packer.

Details of the approved well construction plan are incorporated into this Permit as APPENDIX A. Changes to the approved plan that may occur during construction must be approved by the Director prior to being physically incorporated.

1. Casing and Cement.

The well or wells shall be cased and cemented to prevent the movement of fluids into or between underground sources of drinking water. The well casing and cement shall be designed for the life expectancy of the well and of the grade and size shown in APPENDIX A. Remedial cementing may be required if shown to be inadequate by cement bond log or other attempted demonstration of Part II (External) mechanical integrity.

2. Injection Tubing and Packer.

Injection tubing is required, and shall be run and set with a packer at or below the depth indicated in APPENDIX A. The packer setting depth may be changed provided it remains below the depth indicated in APPENDIX A and the Permittee provides notice and obtains the Director's approval for the change.

3. Sampling and Monitoring Devices.

The Permittee shall install and maintain in good operating condition:

- (a) a "tap" at a conveniently accessible location on the injection flow line between the pump house or storage tanks and the injection well, isolated by shut-off valves, for collection of representative samples of the injected fluid; and
- (b) one-half (1/2) inch female iron pipe fitting, isolated by shut-off valves and located at the wellhead at a conveniently accessible location, for the attachment of a pressure gauge capable of monitoring pressures ranging from normal operating pressures up to the Maximum Allowable Injection Pressure specified in APPENDIX C:
 - (i) on the injection tubing; and
 - (ii) on the tubing-casing annulus (TCA); and
- (c) a pressure actuated shut-off device attached to the injection flow line set to shut-off the injection pump when or before the Maximum Allowable Injection Pressure (MAIP) specified in APPENDIX C is reached at the wellhead; and
- (d) a non-resettable cumulative volume recorder attached to the injection line.

4. Well Logging and Testing

Well logging and testing requirements are found in APPENDIX B. The Permittee shall ensure the log and test requirements are performed within the time frames specified in APPENDIX B. Well logs and tests shall be performed according to current EPA-approved procedures. Well log and test results shall be submitted to the Director within sixty (60) days of completion of the logging or testing activity, and shall include a report describing the methods used during logging or testing and an interpretation of the test or log results.

5. Postponement of Construction or Conversion

The Permittee shall complete well construction within one year of the Effective Date of the Permit, or in the case of an Area Permit within one year of Authorization of the additional well. Authorization to construct and operate shall expire if the well has not been constructed within one year of the Effective Date of the Permit or Authorization and the Permit may be terminated under 40 CFR 144.40, unless the Permittee has notified the Director and requested an extension prior to expiration. Notification shall be in writing, and shall state the reasons for the delay and provide an estimated completion date. Once Authorization has expired under this part, the complete permit process including opportunity for public comment may be required before Authorization to construct and operate may be reissued.

6. Workovers and Alterations

Workovers and alterations shall meet all conditions of the Permit. Prior to beginning any addition or physical alteration to an injection well that may significantly affect the tubing, packer or casing, the Permittee shall give advance notice to the Director and obtain the Director's approval. The Permittee shall record all changes to well construction on a Well Rework Record (EPA Form 7520-12), and shall provide this and any other record of well workover, logging, or test data to EPA within sixty (60) days of completion of the activity.

A successful demonstration of Part I MI is required following the completion of any well workover or alteration which affects the casing, tubing, or packer. Injection operations shall not be resumed until the well has successfully demonstrated mechanical integrity and the Director has provided written approval to resume injection.

Section B. MECHANICAL INTEGRITY

The Permittee is required to ensure each injection well maintains mechanical integrity at all times. The Director, by written notice, may require the Permittee to comply with a schedule describing when mechanical integrity demonstrations shall be made.

An injection well has mechanical integrity if:

- (a) There is no significant leak in the casing, tubing, or packer (Part I); and
- (b) There is no significant fluid movement into an underground source of drinking water through vertical channels adjacent to the injection well bore (Part II).

1. Demonstration of Mechanical Integrity (MI).

The operator shall demonstrate MI prior to commencing injection and periodically thereafter. Well-specific conditions dictate the methods and the frequency for demonstrating MI and are discussed in the Statement of Basis. The logs and tests are designed to demonstrate both internal (Part I) and external (Part II) MI as described above. The conditions present at this well site warrant the methods and frequency required in Appendix B of this Permit.

In addition to these regularly scheduled demonstrations of MI, the operator shall demonstrate internal (Part I) MI after any workover which affects the tubing, packer or casing.

The Director may require additional or alternative tests if the results presented by the operator are not satisfactory to the Director to demonstrate there is no movement of fluid into or between USDWs resulting from injection activity. Results of MI tests shall be submitted to the Director as soon as possible but no later than sixty (60) days after the test is complete.

2. Mechanical Integrity Test Methods and Criteria

EPA-approved methods shall be used to demonstrate mechanical integrity. Ground Water Section Guidance No. 34 "Cement Bond Logging Techniques and Interpretation", Ground Water Section Guidance No. 37, "Demonstrating Part II (External) Mechanical Integrity for a Class II injection well permit", and Ground Water Section Guidance No. 39, "Pressure Testing Injection Wells for Part I (Internal) Mechanical Integrity" are available from EPA and will be provided upon request.

The Director may stipulate specific test methods and criteria best suited for a specific well construction and injection operation.

3. Notification Prior to Testing.

The Permittee shall notify the Director at least 30 days prior to any scheduled mechanical integrity test. The Director may allow a shorter notification period if it would be sufficient to enable EPA to witness the mechanical integrity test. Notification may be in the form of a yearly or quarterly schedule of planned mechanical integrity tests, or it may be on an individual basis.

4. Loss of Mechanical Integrity.

If the well fails to demonstrate mechanical integrity during a test, or a loss of mechanical integrity becomes evident during operation (such as presence of pressure in the TCA, water flowing at the surface, etc.), the Permittee shall notify the Director within 24 hours (see Part III Section E Paragraph 11(e) of this Permit) and the well shall be shut-in within 48 hours unless the Director requires immediate shut-in.

Within five days, the Permittee shall submit a follow-up written report that documents test results, repairs undertaken or a proposed remedial action plan.

Injection operations shall not be resumed until after the well has successfully been repaired and demonstrated mechanical integrity, and the Director has provided approval to resume injection.

Section C. WELL OPERATION

INJECTION BETWEEN THE OUTERMOST CASING PROTECTING UNDERGROUND SOURCES OF DRINKING WATER AND THE WELL BORE IS PROHIBITED.

Injection is approved under the following conditions:

1. Requirements Prior to Commencing Injection.

Well injection, including for new wells authorized by an Area Permit under 40 CFR 144.33 (c), may commence only after all well construction and pre-injection requirements herein have been met and approved. The Permittee may not commence injection until construction is complete, and

- (a) The Permittee has submitted to the Director a notice of completion of construction and a completed EPA Form 7520-10 or 7520-12; all applicable logging and testing requirements of this Permit (see APPENDIX B) have been fulfilled and the records submitted to the Director; mechanical integrity pursuant to 40 CFR 146.8 and Part II Section B of this Permit has been demonstrated; and
 - (i) The Director has inspected or otherwise reviewed the new injection well and finds it is in compliance with the conditions of the Permit; or
 - (ii) The Permittee has not received notice from the Director of his or her intent to inspect or otherwise review the new injection well within 13 days of the date of the notice in Paragraph 1a, in which case prior inspection or review is waived and the Permittee may commence injection.

2. Injection Interval.

Injection is permitted only within the approved injection interval, listed in APPENDIX C. Additional individual injection perforations may be added provided that they remain within the approved injection interval and the Permittee provides notice to the Director in accordance with Part II, Section A, Paragraph 6.

3. Injection Pressure Limitation

- (a) The permitted Maximum Allowable Injection Pressure (MAIP), measured at the wellhead, is found in APPENDIX C. Injection pressure shall not exceed the amount the Director determines is appropriate to ensure that injection does not initiate new fractures or propagate existing fractures in the confining zone adjacent to USDWs. In no case shall injection pressure cause the movement of injection or formation fluids into a USDW.
- (b) The Permittee may request a change of the MAIP, or the MAIP may be increased or decreased by the Director in order to ensure that the requirements in Paragraph (a) above are fulfilled. The Permittee may be required to conduct a step rate injection test or other suitable test to provide information for determining the fracture pressure of the injection zone. Change of the permitted MAIP by the Director shall be by modification of this Permit and APPENDIX C.

4. Injection Volume Limitation.

Injection volume is limited to the total volume specified in APPENDIX C.

5. Injection Fluid Limitation.

Injected fluids are limited to those identified in 40 CFR 144.6(b)(2) as fluids used for enhanced recovery of oil or natural gas, including those which are brought to the surface in connection with conventional oil or natural gas production that may be commingled with waste waters from gas plants which are an integral part of production operations unless those waters are classified as a hazardous waste at the time of injection, pursuant to 40 CFR 144.6(b). Non-exempt wastes, including unused fracturing fluids or acids, gas plant cooling tower cleaning wastes, service wastes and vacuum truck wastes, are NOT approved for injection. This well is NOT approved for commercial brine injection, industrial waste fluid disposal or injection of hazardous waste as defined by CFR 40 Part 261. The Permittee shall provide a listing of the sources of injected fluids in accordance with the reporting requirements in Part II Section D Paragraph 4 and APPENDIX D of this Permit.

6. Tubing-Casing Annulus (TCA)

The tubing-casing annulus (TCA) shall be filled with water treated with a corrosion inhibitor, or other fluid approved by the Director. The TCA valve shall remain closed during normal operating conditions and the TCA pressure shall be maintained at zero (0) psi.

If TCA pressure cannot be maintained at zero (0) psi, the Permittee shall follow the procedures in Ground Water Section Guidance No. 35 "Procedures to follow when excessive annular pressure is observed on a well."

Section D. MONITORING, RECORDKEEPING, AND REPORTING OF RESULTS

1. Monitoring Parameters, Frequency, Records and Reports.

Monitoring parameters are specified in APPENDIX D. Pressure monitoring recordings shall be taken at the wellhead. The listed parameters are to be monitored, recorded and reported at the frequency indicated in APPENDIX D even during periods when the well is not operating.

Monitoring records must include:

- (a) the date, time, exact place and the results of the observation, sampling, measurement, or analysis, and;
- (b) the name of the individual(s) who performed the observation, sampling, measurement, or analysis, and;
- (c) the analytical techniques or methods used for analysis.

2. Monitoring Methods.

- (a) Monitoring observations, measurements, samples, etc. taken for the purpose of complying with these requirements shall be representative of the activity or condition being monitored.

- (b) Methods used to monitor the nature of the injected fluids must comply with analytical methods cited and described in Table 1 of 40 CFR 136.3 or Appendix III of 40 CFR 261, or by other methods that have been approved in writing by the Director.
- (c) Injection pressure, annulus pressure, injection rate, and cumulative injected volumes shall be observed and recorded at the wellhead under normal operating conditions, and all parameters shall be observed simultaneously to provide a clear depiction of well operation.
- (d) Pressures are to be measured in pounds per square inch (psi).
- (e) Fluid volumes are to be measured in standard oil field barrels (bbl).
- (f) Fluid rates are to be measured in barrels per day (bbl/day).

3. Records Retention.

- (a) Records of calibration and maintenance, and all original strip chart recordings for continuous monitoring instrumentation, copies of all reports required by this permit, and records of all data used to complete the application for this permit shall be retained for a period of AT LEAST THREE (3) YEARS from the date of the sample, measurement, report, or application. This period may be extended anytime prior to its expiration by request of the Director.
- (b) Records of the nature and composition of all injected fluids must be retained until three (3) years after the completion of any plugging and abandonment (P&A) procedures specified under 40 CFR 144.52(a)(6) or under Part 146 Subpart G, as appropriate. The Director may require the Permittee to deliver the records to the Director at the conclusion of the retention period. The Permittee shall continue to retain the records after the three (3) year retention period unless the Permittee delivers the records to the Director or obtains written approval from the Director to discard the records.
- (c) The Permittee shall retain records at the location designated in APPENDIX D.

4. Annual Reports.

Whether the well is operating or not, the Permittee shall submit an Annual Report to the Director that summarizes the results of the monitoring required by Part II Section D and APPENDIX D.

The first Annual Report shall cover the period from the effective date of the Permit through December 31 of that year. Subsequent Annual Reports shall cover the period from January 1 through December 31 of the reporting year. Annual Reports shall be submitted by February 15 of the year following data collection. EPA Form 7520-11 may be copied and shall be used to submit the Annual Report, however, the monitoring requirements specified in this Permit are mandatory even if EPA Form 7520-11 indicates otherwise.

Section E. PLUGGING AND ABANDONMENT

1. Notification of Well Abandonment, Conversion or Closure.

The Permittee shall notify the Director in writing at least forty-five (45) days prior to: 1) plugging and abandoning an injection well, 2) converting to a non-injection well, and 3) in the case of an Area Permit, before closure of the project.

2. Well Plugging Requirements

Prior to abandonment, the injection well shall be plugged with cement in a manner which isolates the injection zone and prevents the movement of fluids into or between underground sources of drinking water, and in accordance with 40 CFR 146.10 and other applicable Federal, State or local law or regulations. Tubing, packer and other downhole apparatus shall be removed. Cement with additives such as accelerators and retarders that control or enhance cement properties may be used for plugs; however, volume-extending additives and gel cements are not approved for plug use. Plug placement shall be verified by tagging. Plugging gel of at least 9.6 lb/gal shall be placed between all plugs. A minimum 50 ft surface plug shall be set inside and outside of the surface casing to seal pathways for fluid migration into the subsurface. The Plugging Record must be certified as accurate and complete by the person responsible for the plugging operation. Prior to placement of the cement plug(s) the well shall be in a state of static equilibrium with the mud weight equalized top to bottom, either by circulating the mud in the well at least once or by a comparable method prescribed by the Director.

3. Approved Plugging and Abandonment Plan.

The approved plugging and abandonment plan is incorporated into this Permit as APPENDIX E. Changes to the approved plugging and abandonment plan must be approved by the Director prior to beginning plugging operations. The Director also may require revision of the approved plugging and abandonment plan at any time prior to plugging the well.

4. Forty Five (45) Day Notice of Plugging and Abandonment.

The Permittee shall notify the Director at least forty-five (45) days prior to plugging and abandoning a well and provide notice of any anticipated change to the approved plugging and abandonment plan.

5. Plugging and Abandonment Report.

Within sixty (60) days after plugging a well, the Permittee shall submit a report (EPA Form 7520-13) to the Director. The plugging report shall be certified as accurate by the person who performed the plugging operation. Such report shall consist of either:

- (a) A statement that the well was plugged in accordance with the approved plugging and abandonment plan; or
- (b) Where actual plugging differed from the approved plugging and abandonment plan, an updated version of the plan, on the form supplied by the Director, specifying the differences.

6. Inactive Wells.

After any period of two years during which there is no injection the Permittee shall plug and abandon the well in accordance with Part II Section E Paragraph 2 of this Permit unless the Permittee:

- (a) Provides written notice to the Director;
- (b) Describes the actions or procedures the Permittee will take to ensure that the well will not endanger USDWs during the period of inactivity. These actions and procedures shall include compliance with mechanical integrity demonstration, Financial Responsibility and all other permit requirements designed to protect USDWs; and
- (c) Receives written notice by the Director temporarily waiving plugging and abandonment requirements.

PART III. CONDITIONS APPLICABLE TO ALL PERMITS

Section A. EFFECT OF PERMIT

The Permittee is allowed to engage in underground injection in accordance with the conditions of this Permit. The Permittee shall not construct, operate, maintain, convert, plug, abandon, or conduct any other activity in a manner that allows the movement of fluid containing any contaminant into underground sources of drinking water, if the presence of that contaminant may cause a violation of any primary drinking water regulation under 40 CFR 142 or may otherwise adversely affect the health of persons. Any underground injection activity not authorized by this Permit or by rule is prohibited. Issuance of this Permit does not convey property rights of any sort or any exclusive privilege; nor does it authorize any injury to persons or property, any invasion of other private rights, or any infringement of any other Federal, State or local law or regulations. Compliance with the terms of this Permit does not constitute a defense to any enforcement action brought under the provisions of Section 1431 of the Safe Drinking Water Act (SDWA) or any other law governing protection of public health or the environment, for any imminent and substantial endangerment to human health or the environment, nor does it serve as a shield to the Permittee's independent obligation to comply with all UIC regulations. Nothing in this Permit relieves the Permittee of any duties under applicable regulations.

Section B. CHANGES TO PERMIT CONDITIONS

1. Modification, Reissuance, or Termination.

The Director may, for cause or upon a request from the Permittee, modify, revoke and reissue, or terminate this Permit in accordance with 40 CFR 124.5, 144.12, 144.39, and 144.40. Also, this Permit is subject to minor modification for causes as specified in 40 CFR 144.41. The filing of a request for modification, revocation and reissuance, termination, or the notification of planned changes or anticipated noncompliance on the part of the Permittee does not stay the applicability or enforceability of any condition of this Permit.

2. Conversions.

The Director may, for cause or upon a written request from the Permittee, allow conversion of the well from a Class II injection well to a non-Class II well. Conversion may not proceed until the Permittee receives written approval from the Director. Conditions of such conversion may include but are not limited to, approval of the proposed well rework, follow up demonstration of mechanical integrity, well-specific monitoring and reporting following the conversion, and demonstration of practical use of the converted configuration.

3. Transfer of Permit.

Under 40 CFR 144.38, this Permit is transferable provided the current Permittee notifies the Director at least thirty (30) days in advance of the proposed transfer date (EPA Form 7520-7) and provides a written agreement between the existing and new Permittees containing a specific date for transfer of Permit responsibility, coverage and liability between them. The notice shall adequately demonstrate that the financial responsibility requirements of 40 CFR 144.52(a)(7) will be met by the new Permittee. The Director may require modification or revocation and reissuance of the Permit to change the name of the Permittee and incorporate such other requirements as may be necessary under the Safe Drinking Water Act; in some cases, modification or revocation and reissuance is mandatory.

4. Permittee Change of Address.

Upon the Permittee's change of address, or whenever the operator changes the address where monitoring records are kept, the Permittee must provide written notice to the Director within 30 days.

5. Construction Changes, Workovers, Logging and Testing Data

The Permittee shall give advance notice to the Director, and shall obtain the Director's written approval prior to any physical alterations or additions to the permitted facility. Alterations or workovers shall meet all conditions as set forth in this permit. The Permittee shall record any changes to the well construction on a Well Rework Record (EPA Form 7520-12), and shall provide this and any other record of well workovers, logging, or test data to EPA within sixty (60) days of completion of the activity.

Following the completion of any well workovers or alterations which affect the casing, tubing, or packer, a successful demonstration of mechanical integrity (Part III, Section F of this Permit) shall be made, and written authorization from the Director received, prior to resuming injection activities.

Section C. SEVERABILITY

The Provisions of this Permit are severable, and if any provision of this Permit or the application of any provision of this Permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this Permit shall not be affected thereby.

Section D. CONFIDENTIALITY

In accordance with 40 CFR Part 2 and 40 CFR 144.5, information submitted to EPA pursuant to this Permit may be claimed as confidential by the submitter. Any such claim must be asserted at the time of submission by stamping the words "confidential business information" on each page containing such information. If no claim is made at the time of submission, EPA may make the information available to the public without further notice. If a claim is asserted, the validity of the claim will be assessed in accordance with the procedures in 40 CFR Part 2 (Public Information). Claims of confidentiality for the following information will be denied:

- The name and address of the Permittee, and
- information which deals with the existence, absence or level of contaminants in drinking water.

Section E. GENERAL PERMIT REQUIREMENTS

1. Duty to Comply.

The Permittee must comply with all conditions of this Permit. Any noncompliance constitutes a violation of the Safe Drinking Water Act (SDWA) and is grounds for enforcement action; for Permit termination, revocation and reissuance, or modification; or for denial of a permit renewal application; except that the Permittee need not comply with the provisions of this Permit to the extent and for the duration such noncompliance is authorized in an emergency permit under 40 CFR 144.34. All violations of the SDWA may subject the Permittee to penalties and/or criminal prosecution as specified in Section 1423 of the SDWA.

2. Duty to Reapply.

If the Permittee wishes to continue an activity regulated by this Permit after the expiration date of this Permit, under 40 CFR 144.37 the Permittee must apply for a new permit prior to the expiration date.

3. Need to Halt or Reduce Activity Not a Defense.

It shall not be a defense for a Permittee in an enforcement action that it would have been necessary to halt or reduce the permitted activity in order to maintain compliance with the conditions of this Permit.

4. Duty to Mitigate.

The Permittee shall take all reasonable steps to minimize or correct any adverse impact on the environment resulting from noncompliance with this Permit.

5. Proper Operation and Maintenance.

The Permittee shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the Permittee to achieve compliance with the conditions of this Permit. Proper operation and maintenance includes effective performance, adequate funding, adequate operator staffing and training, and adequate laboratory and process controls, including appropriate quality assurance procedures. This provision requires the operation of back-up or auxiliary facilities or similar systems only when necessary to achieve compliance with the conditions of this Permit.

6. Permit Actions.

This Permit may be modified, revoked and reissued or terminated for cause. The filing of a request by the Permittee for a permit modification, revocation and reissuance, or termination, or a notification of planned changes or anticipated noncompliance, does not stay any permit condition.

7. Property Rights.

This Permit does not convey any property rights of any sort, or any exclusive privilege.

8. Duty to Provide Information.

The Permittee shall furnish to the Director, within a time specified, any information which the Director may request to determine whether cause exists for modifying, revoking and reissuing, or terminating this permit, or to determine compliance with this permit. The Permittee shall also furnish to the Director, upon request, copies of records required to be kept by this Permit. The Permittee is required to submit any information required by this Permit or by the Director to the mailing address designated in writing by the Director.

9. Inspection and Entry.

The Permittee shall allow the Director, or an authorized representative, upon the presentation of credentials and other documents as may be required by law, to:

- (a) Enter upon the Permittee's premises where a regulated facility or activity is located or conducted, or where records must be kept under the conditions of this Permit;

- (b) Have access to and copy, at reasonable times, any records that must be kept under the conditions of this Permit;
- (c) Inspect at reasonable times any facilities, equipment (including monitoring and control equipment), practices, or operations regulated or required under this Permit; and,
- (d) Sample or monitor at reasonable times, for the purpose of assuring permit compliance or as otherwise authorized by the SDWA, any substances or parameters at any location.

10. Signatory Requirements.

All applications, reports or other information submitted to the Director shall be signed and certified according to 40 CFR 144.32. This section explains the requirements for persons duly authorized to sign documents, and provides wording for required certification.

11. Reporting Requirements.

- (a) **Planned changes.** The Permittee shall give notice to the Director as soon as possible of any planned changes, physical alterations or additions to the permitted facility, and prior to commencing such changes.
- (b) **Anticipated noncompliance.** The Permittee shall give advance notice to the Director of any planned changes in the permitted facility or activity which may result in noncompliance with permit requirements.
- (c) **Monitoring Reports.** Monitoring results shall be reported at the intervals specified in this Permit.
- (d) **Compliance schedules.** Reports of compliance or noncompliance with, or any progress reports on, interim and final requirements contained in any compliance schedule of this Permit shall be submitted no later than 30 days following each schedule date.
- (e) **Twenty-four hour reporting.** The Permittee shall report to the Director any noncompliance which may endanger human health or the environment, including:
 - (i) Any monitoring or other information which indicates that any contaminant may cause endangerment to a USDW; or
 - (ii) Any noncompliance with a permit condition or malfunction of the injection system which may cause fluid migration into or between USDWs.

Information shall be provided, either directly or by leaving a message, within twenty-four (24) hours from the time the permittee becomes aware of the circumstances by telephoning (800) 227-8917 and requesting EPA Region VIII UIC Program Compliance and Technical Enforcement Director, or by contacting the EPA Region VIII Emergency Operations Center at (303) 293-1788.

In addition, a follow up written report shall be provided to the Director within five (5) days of the time the Permittee becomes aware of the circumstances. The written submission shall contain a description of the noncompliance and its cause, the period of noncompliance including exact dates and times, and if the noncompliance has not been corrected the anticipated time it is expected to continue; and the steps taken or planned to reduce, eliminate, and prevent recurrence of the noncompliance.

- (f) Oil Spill and Chemical Release Reporting: The Permittee shall comply with all reporting requirements related to the occurrence of oil spills and chemical releases by contacting the National Response Center (NRC) at (800) 424-8802, (202) 267-2675, or through the NRC website <http://www.nrc.uscg.mil/index.htm>.
- (g) Other Noncompliance. The Permittee shall report all instances of noncompliance not reported under paragraphs Part III, Section E Paragraph 11(b) or Section E, Paragraph 11(e) at the time the monitoring reports are submitted. The reports shall contain the information listed in Paragraph 11(e) of this Section.
- (h) Other information. Where the Permittee becomes aware that it failed to submit any relevant facts in the permit application, or submitted incorrect information in a permit application or in any report to the Director, the Permittee shall promptly submit such facts or information to the Director.

Section F. FINANCIAL RESPONSIBILITY

1. Method of Providing Financial Responsibility.

The Permittee shall maintain continuous compliance with the requirement to maintain financial responsibility and resources to close, plug, and abandon the underground injection well(s). No substitution of a demonstration of financial responsibility shall become effective until the Permittee receives written notification from the Director that the alternative demonstration of financial responsibility is acceptable. The Director may, on a periodic basis, require the holder of a permit to revise the estimate of the resources needed to plug and abandon the well to reflect changes in such costs and may require the Permittee to provide a revised demonstration of financial responsibility.

2. Insolvency.

In the event of:

- (a) the bankruptcy of the trustee or issuing institution of the financial mechanism; or
- (b) suspension or revocation of the authority of the trustee institution to act as trustee; or

- (c) the institution issuing the financial mechanism losing its authority to issue such an instrument

the Permittee must notify the Director in writing, within ten (10) business days, and the Permittee must establish other financial assurance or liability coverage acceptable to the Director within sixty (60) days after any event specified in (a), (b), or (c) above.

The Permittee must also notify the Director by certified mail of the commencement of voluntary or involuntary proceedings under Title 11 (Bankruptcy), U.S. Code naming the owner or operator as debtor, within ten (10) business days after the commencement of the proceeding. A guarantor, if named as debtor of a corporate guarantee, must make such a notification as required under the terms of the guarantee.

APPENDIX A

WELL CONSTRUCTION REQUIREMENTS

See diagram.

The Federal No. 11-7-9-18 was drilled to a depth of 5865 feet (KB) in the Basal Carbonate Member of the Green River Formation.

Surface Casing (8-5/8") was set to a depth of 317' in a 12-1/4" hole using 160 sacks of Class "G" cement which was circulated to the surface.

Production casing (5-1/2") was set at a depth of 5843' (KB) in a 7-7/8" hole with 350 sacks of Premium Lite II and 450 sacks of 50/50 POZ mix. This well construction is considered adequate to protect USDWs.

The EPA calculates the top of cement as 700 feet from the surface. The Cement Bond Log (CBL) identifies the top of cement at 130'. CBL analysis does not identify adequate 80% bond index within the confining zone.

The schematic diagram shows enhanced recovery injection perforations in the Douglas Creek Member of the Green River Formation. Additional perforations may be added at a later time between the depths of 3594 feet and the top of the Wasatch Formation (estimated to be 5880 feet) provided the operator first notifies the Director and later submits an updated well completion report (EPA Form 7520-12) and a schematic diagram.

The packer will be set no higher than 100 feet above the top perforation.

UT21092-07351

Federal 11-7-9-18

Spud Date: 6-8-05
Put on Production: 7-15-05
GL: 5072' KB: 5084'

Initial Production: BOPD 63,
MCFD 4, BWPD 141

Proposed Injection
Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (305.24')
DEPTH LANDED: 317.09' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 160 sxs Class "C" emt, est 4 bbls emt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 138 jts. (5829.44')
DEPTH LANDED: 5842.69' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 350 sxs Prem. Lit. II & 450 sxs 50/50 POZ.
CEMENT TOP AT: 130'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55
NO. OF JOINTS: 177 jts (5637.31')
TUBING ANCHOR: 5549.31' KB
NO. OF JOINTS: 1 jts (31.43')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5883.54' KB
NO. OF JOINTS: 2 jts (62.16')
TOTAL STRING LENGTH: BOT @ 5647.25' KB


FRAC JOB

7-11-05 5566-5590' Frac CP3 sand as follows:
60,749#s 20/40 sand in 495 bbls Lightning
17 frac fluid. Treated @ avg press of 1300 psi
Calc flush: 5564 gal. Actual flush: 5754 gal.

7-11-05 5387-5467' Frac CP1 & CP2 sand as follows:
69,628#s 20/40 sand in 550 bbls Lightning
17 frac fluid. Treated @ avg press of 1200 psi
w/avg rate of 25.4 BPM. ISIP 1450 psi. Calc
flush: 5385 gal. Actual flush: 5376 gal.

7-11-05 5004-5047' Frac A3 & A1 sand as follows:
120,297#s 20/40 sand in 844 bbls Lightning
17 frac fluid. Treated @ avg press of 1319 psi
w/avg rate of 25.4 BPM. ISIP 1750 psi. Calc
flush: 2002 gal. Actual flush: 5040 gal.

7-12-05 4801-4809' Frac B1 sand as follows:
25,544#s 20/40 sand in 273 bbls Lightning
17 frac fluid. Treated @ avg press of 1794 psi
w/avg rate of 25.2 BPM. ISIP 2250 psi. Calc
flush: 4799 gal. Actual flush: 4704 gal.



PERFORATION RECORD

Date	Interval	JSPP	Holes
7-1-05	5566-5590'	4 JSPP	96 holes
7-11-05	5456-5467'	4 JSPP	14 holes
7-11-05	5387-5400'	4 JSPP	52 holes
7-11-05	5040-5047'	4 JSPP	28 holes
7-11-05	5004-5020'	4 JSPP	64 holes
7-11-05	4801-4809'	4 JSPP	32 holes

UT-21092-07351

NEWFIELD

Federal 11-7-9-18

Section 7-T9S-R18E
NE 1/4 Section 7-T9S-R18E
Utah Co. Utah
API # 43-047-35451; Lease # 1711-16540

APPENDIX B

LOGGING AND TESTING REQUIREMENTS

Logs.

Logs will be conducted according to current UIC guidance. It is the responsibility of the Permittee to obtain and use guidance prior to conducting any well logging required as a condition of this permit.

NO LOGGING REQUIREMENTS

Tests.

Tests will be conducted according to current UIC guidance. It is the responsibility of the Permittee to obtain and use guidance prior to conducting any well test required as a condition of this permit.

WELL NAME: Federal 11-7-9-18	
TYPE OF TEST	DATE DUE
Radioactive Tracer Survey (2)	Within a 180-day limited to inject period and once every five-year period following the last successful test.
Pore Pressure	Prior to receiving authorization to begin injection.
Standard Annulus Pressure	Prior to receiving authorization to inject and at least once every five years after the last successful demonstration of Part I Mechanical Integrity.

APPENDIX C

OPERATING REQUIREMENTS

MAXIMUM ALLOWABLE INJECTION PRESSURE:

Maximum Allowable Injection Pressure (MAIP) as measured at the surface shall not exceed the pressure(s) listed below.

WELL NAME	MAXIMUM ALLOWED INJECTION PRESSURE (psi)
	ZONE 1 (Upper)
Federal 11-7-9-18	1,105

INJECTION INTERVAL(S):

Injection is permitted only within the approved injection interval listed below. Injection perforations may be altered provided they remain within the approved injection interval and the Permittee provides notice to the Director in accordance with Part II, Section A, Paragraph 6. Specific injection perforations can be found in Appendix A.

WELL NAME: Federal 11-7-9-18			
FORMATION NAME	APPROVED INJECTION INTERVAL (KB, ft)		FRACTURE GRADIENT (psi/ft)
	TOP	BOTTOM	
Green River	3,594.00 - 5,880.00		0.670

ANNULUS PRESSURE:

The annulus pressure shall be maintained at zero (0) psi as measured at the wellhead. If this pressure cannot be maintained, the Permittee shall follow the procedures listed under Part II, Section C. 6. of this permit.

MAXIMUM INJECTION VOLUME:

There is no limitation on the number of barrels per day (bbls/day) of water that shall be injected into this well, provided further that in no case shall injection pressure exceed that limit shown in Appendix C.

APPENDIX D

MONITORING AND REPORTING PARAMETERS

This is a listing of the parameters required to be observed, recorded, and reported. Refer to the permit Part II, Section D, for detailed requirements for observing, recording, and reporting these parameters.

OBSERVE MONTHLY AND RECORD AT LEAST ONCE EVERY THIRTY DAYS	
OBSERVE AND RECORD	Injection pressure (psig)
	Annulus pressure(s) (psig)
	Injection rate (bbl/day)
	Fluid volume injected since the well began injecting (bbls)
ANNUALLY	
ANALYZE	Injected fluid total dissolved solids (mg/l)
	Injected fluid specific gravity
	Injected fluid specific conductivity
	Injected fluid pH
ANNUALLY	
REPORT	Each month's maximum and averaged injection pressures (psig)
	Each month's maximum and minimum annulus pressure(s) (psig)
	Each month's injected volume (bbl)
	Fluid volume injected since the well began injecting (bbl)
	Written results of annual injected fluid analysis
	Sources of all fluids injected during the year

In addition to these items, additional Logging and Testing results may be required periodically. For a list of those items and their due dates, please refer to APPENDIX B - LOGGING AND TESTING REQUIREMENTS.

Records of all monitoring activities must be retained and made available for inspection at the following location:

APPENDIX E

PLUGGING AND ABANDONMENT REQUIREMENTS

See diagram.

The well shall be plugged in a manner that isolates the injection zone and prevents movement of fluids into or between USDWs, and in compliance with other federal, state, and local regulations. Tubing, packer, and other downhole apparatus shall be removed. Cement properties may be used for plugs; however, volume-extending additives and gel cements are not approved for plug use. Plug placement shall be verified by tagging. Plugging gel of at least 9.2 lb/gal shall be placed between all plugs. A minimum 50 ft surface plug shall be set inside and outside of the surface casing to seal pathways for fluid migration into the subsurface. Within sixty days after plugging the owner or operator shall submit Plugging Record (EPA Form 7520-13) to the Director. The Plugging Record must be certified as accurate and complete by the person responsible for the plugging operation. At a minimum, the following plugs are required:

PLUG 1: Seal injection zone: Set a Cast Iron Bridge Plug (CIBP) no more than 50 ft above the top perforation. Place at least 20 ft of cement on top of the CIBP.

PLUG 2: Seal Mahogany Shale and Trona intervals: Squeeze a cement plug on the backside of the 5-1/2 inch casing across the Trona Zone and the Mahogany Shale at approximately 2,792 ft (unless preexisting backside cement precludes cement-squeezing this interval) followed by a minimum 150 ft balanced cement plug inside the 5-1/2 inch casing across the Trona Zone and the Mahogany Shale, approximately 2,718 to 2,868 ft.

PLUG 3: Seal USDWs: Squeeze a cement plug at approximately 1,279 ft on the backside of the 5-1/2 inch casing across the base of the Uinta/Top of the Green River Formation (unless pre-existing backside cement precludes cement-squeezing this interval), followed by a minimum 100 ft balanced cement plug inside the 5-1/2 inch casing across the base of the Uinta/Top of the Green River Formation, with the mid-contact point set at approximately 1,279 ft., with the cement encompassing the depths of approximately 1,229 to 1,329 ft.

PLUG 4: Seal surface: Set a Class G cement plug within the 5-1/2 inch casing to 366 ft and up the 5-1/2 inch by 8-5/8 inch casings annulus to surface.

UT 21092-07351

Federal 11-7-9-18

Spud Date: 6-8-05
 Put on Production: 7-15-05
 GL: 50727' K10: 5084'


Proposed P&A
 Wellbore Diagram

SURFACE CASING

CASG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 21#
 LENGTH: 7 jls. (305.24')
 DEPTH LANDED: 317.09' KB
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 160 sxs Class "G" cement, est 4 bbls cement to surf

PRODUCTION CASING

CASG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 138 jls. (5829.44')
 DEPTH LANDED: 5842.69' KB
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 350 sxs Prem. Lite II & 450 sxs 50/50 POZ.
 CEMENT TOP AT: 130'



UT 21092-07351

NEWFIELD

Federal 11-7-9-18
 1980' FSL & 1977' FWL
 NE SW Section 7-T9S-R18E
 Uintah Co. Utah
 API - 43-047-35451; Lease # UTH - 16540

APPENDIX F

CORRECTIVE ACTION REQUIREMENTS

No corrective action is deemed necessary for this project.

STATEMENT OF BASIS

NEWFIELD PRODUCTION COMPANY

**FEDERAL 11-7-9-18
UINTAH COUNTY, UT**

EPA PERMIT NO. UT21092-07351

CONTACT: Bruce Suchomel
U. S. Environmental Protection Agency
Ground Water Program, 8P-W-GW
1595 Wynkoop Street
Denver, Colorado 80202-1129
Telephone: 1-800-227-8917 ext. 312-6001

This STATEMENT OF BASIS gives the derivation of site-specific UIC Permit conditions and reasons for them. Referenced sections and conditions correspond to sections and conditions in the Permit.

EPA UIC permits regulate the injection of fluids into underground injection wells so that the injection does not endanger underground sources of drinking water. EPA UIC permit conditions are based upon the authorities set forth in regulatory provisions at 40 CFR Parts 144 and 146, and address potential impacts to underground sources of drinking water. Under 40 CFR 144.35 Issuance of this permit does not convey any property rights of any sort or any exclusive privilege, nor authorize injury to persons or property or invasion of other private rights, or any infringement of other Federal, State or local laws or regulations. Under 40 CFR 144 Subpart D, certain conditions apply to all UIC Permits and may be incorporated either expressly or by reference. General Permit conditions for which the content is mandatory and not subject to site-specific differences (40 CFR Parts 144, 146 and 147) are not discussed in this document.

Upon the Effective Date when issued, the Permit authorizes the construction and operation of injection wells so that the injection does not endanger underground sources of drinking water, governed by the conditions specified in the Permit. The Permit is issued for the operating life of the injection well or project unless terminated for reasonable cause under 40 CFR 144.39, 144.40 and 144.41. The Permit is subject to EPA review at least once every five (5) years to determine if action is required under 40 CFR 144.36(a).

PART I. General Information and Description of Facility

Newfield Production Company
1001 Seventeenth Street, Suite 2000
Denver, CO 80202

on

August 7, 2006

submitted an application for an Underground Injection Control (UIC) Program Permit or Permit Modification for the following injection well or wells:

Federal 11-7-9-18
1980' FSL & 1977' FWL, NESW S7, T9S, R18E
Uintah County, UT

Regulations specific to Uintah-Ouray Indian Reservation injection wells are found at 40 CFR 147 Subpart TT.

The application, including the required information and data necessary to issue or modify a UIC Permit in accordance with 40 CFR Parts 144, 146 and 147, was reviewed and determined by EPA to be complete.

The Permit will expire upon delegation of primary enforcement responsibility (primacy) for applicable portions of the UIC Program to the Ute Indian Tribe or the State of Utah unless the delegated agency has the authority and chooses to adopt and enforce this Permit as a Tribal or State Permit.

TABLE 1.1 shows the status of the well or wells as "New", "Existing", or "Conversion" and for Existing shows the original date of injection operation. Well authorization "by rule" under 40 CFR Part 144 Subpart C expires automatically on the Effective Date of an issued UIC Permit.

The Federal No.11-7-9-18 is currently an active Green River Formation Garden Gulch and Douglas Creek Member oil well. It is the initial intent of the applicant to use the current production perforations for Class II enhanced recovery injection. The Federal 11-7-9-18 has total depth in the Basal Carbonate Member.

TABLE 1.1
WELL STATUS / DATE OF OPERATION

NEW WELLS

Well Name	Well Status	Date of Operation
Federal 11-7-9-18	New	N/A

PART II. Permit Considerations (40 CFR 146.24)

Hydrogeologic Setting

Water wells for domestic supply in this area, when present, generally are completed into the shallow alluvium, the Duchesne River Formation, or the underlying Uinta Formation, and the water generally contains approximately 500 to 1,500 mg/l and higher total dissolved solids.

The Uinta-Animas aquifer in the Uinta Basin is present in water-yielding beds of sandstone, conglomerate, and siltstone of the Duchesne River and Uinta Formations, the Renegade Tongue of the Wasatch Formation, and the Douglas Creek Member of the Green River Formation. The Renegade Tongue of the Wasatch Formation and the Douglas Creek Member of the Green River formation contain an aquifer along the southern and eastern margins of the basin where the rocks primarily consist of fluvial, massive, irregularly bedded sandstone and siltstone. Water-yielding units in the Uinta-Animas aquifer in the Uinta Basin commonly are separated from each other and from the underlying Mesaverde aquifer by units of low permeability composed of claystone, shale, marlstone, or limestone. In the Uinta Basin, for example, the part of the aquifer in the Duchesne River and Uinta formations ranges in thickness from 0 feet at the southern margin of the aquifer to as much as 9,000 feet in the north-central part of the aquifer. Ground-water recharge to the Uinta-Animas aquifer generally occurs in the areas of higher altitude along the margins of the basin. Ground water is discharged mainly to streams, springs, and by transportation from vegetation growing along stream valleys. The rate of ground-water withdrawal is small, and natural discharge is approximately equal to recharge. Recharge occurs near the southern margin of aquifer, and discharge occurs near the White and Green Rivers (from USGS publication H 730-C). Water samples from Mesaverde sands in the nearby Natural Buttes Unit yielded highly saline water.

Geologic Setting (TABLE 2.1)

The proposed enhanced oil recovery injection well is located in the Greater Monument Butte Field, T9S and R17E, which lies near the center of the broad, gently northward dipping south flank of the Uinta Basin. More than 450 million barrels of oil (63MT) have been produced from sediments of the Uinta Basin. The Uinta Basin is a topographic and structural trough encompassing an area of more than 9,300 square miles (14,900 sq. km) in northeast Utah. The basin is sharply asymmetrical, with a steep north flank bounded by the east-west-trending Uinta Mountains, and a gently dipping south flank. The Uinta Basin was formed in Paleocene to Eocene time, creating a large area of internal drainage which was filled by the ancestral Lake Uinta. The lacustrine, or fresh water lake-formed, sediments deposited in and around Lake Uinta make up the Uintah and Green River Formations. The southern shore of Lake Uinta was very broad and flat, resulting in large cyclic shifts of the location of the shoreline during the many repeated transgressive and regressive cycles caused by the climatic and tectonic-induced rise and fall of water levels of the lake. Distributary-mouth bars, distributary channels, and near-shore bars are the primary oil producing sandstone reservoirs in the area. (Ref: "Reservoir Characterization of the Lower Green River Formation, Southwest Uinta Basin, Utah Biannual Technical Progress Report, 4/1/99-9/30/99", by C.D. Morgan, Program Manager, November 1999, Contract DE-AC26-98BC15103).

The Duchesne River Formation is absent in this area. Shale and siltstone of the Uinta Formation outcrop and compose the surface rock throughout the area. The lower 600 ft. to 800 ft. of the Uinta Formation, Consisting generally of shale interbedded with occasionally water-bearing sandstone lenses between 5 ft to 20 ft thick, is underlain by the Green River Formation. The Green River Formation is further subdivided into several Member and local marker units. The

cyclic nature of Green River deposition in the southern shore area resulted in numerous stacked, intertonguing deltaic and near-shore sand and silt deposits. Red alluvial shale and siltstone deposits that intertongue with the Green River sediments are of the Colton and Wasatch Formations. Under the Wasatch Formation is the Mesaverde Formation, which consists primarily of continental-origin deposits of interbedded shale, sandstone, and coal.

The geologic dip is about 200'/mile, and there are no known surface faults in this area. Veins of gilsonite, a natural resinous hydrocarbon occasionally mined as a resource, occurs in the greater Uintah Basin though it is predominantly found on the eastern margin of the basin near the Colorado border. Vertical veins, generally between 2 ft to 6 ft wide but up to 28 ft wide, may extend many miles in length and occasionally extend as deep as 2,000 ft. In this area within the Greater Monument Butte Field there is one known gilsonite vein. This vein is not considered to present a pathway for migration of fluid out of the injection zone because it terminates at depth of about 2,000 ft, far above the protective confining layer and much deeper injection zone. Newfield and the owner of this former gilsonite mine have agreed to conditions for operation near this vein to ensure no potential for impact to this vein or to ground water from enhanced oil recovery operations.

TABLE 2.1
GEOLOGIC SETTING
Federal 11-7-9-18

Formation Name	Top (ft)	Base (ft)	TDS (mg/l)	Lithology
Uinta	0	1,279	10,000	Predominantly lenticular fluvial sand and shale with minor lacustrine carbonates.
Green River	1,279	3,594		Tight sandstone and interbedded shale forming confining layers between individual permeable lenticular sandstone.
Green River: Trona	2,768	2,815		Sodium carbonate.
Green River: Mahogany Bench	2,815	2,832		Oil shale.
Green River Shale (CZ)	3,560	3,594		Shale.
Green River: Garden Gulch Mbr	3,594	4,572	> 10,000	Lacustrine sand, shale, carbonate, interbedded with fluvial sandstone.
Green River: Douglas Creek Mbr.	4,572	5,755	> 10,000	Interbedded sand, shale, and limestone.
Green River: Basal Carbonate	5,755	5,880	> 10,000	Limestone

Proposed Injection Zone(s) (TABLE 2.2)

An injection zone is a geological formation, group of formations, or part of a formation that receives fluids through a well. The proposed injection zones are listed in TABLE 2.2.

Injection will occur into an injection zone that is separated from USDWs by a confining zone which is free of known open faults or fractures within the Area of Review.

The Environmental Protection Agency (EPA) approved interval for Class II enhanced recovery injection in the Federal No. 11-7-9-18 is located between the top of the Garden Gulch Member

(3594 feet) and the top of the Wasatch Formation, estimated to be 5880 feet.

TABLE 2.2
INJECTION ZONES
Federal 11-7-9-18

Formation Name	Top (ft)	Base (ft)	TDS (mg/l)	Fracture Gradient (psi/ft)	Porosity	Exempted?*
Green River	3,594	5,880	> 10,000	0.670		N/A

* C - Currently Exempted
E - Previously Exempted
P - Proposed Exemption
N/A - Not Applicable

Confining Zone(s) (TABLE 2.3)

A confining zone is a geological formation, part of a formation, or a group of formations that limits fluid movement above the injection zone. The confining zone or zones are listed in TABLE 2.3.

The 34-foot (3560 to 3594 feet) shale and argillaceous siltstone Confining Zone directly overlies the Garden Gulch Member.

The State of Utah Division of Water Rights (<http://nrwt1.nr.state.ut.us/wrinfo/query.asp>), identifies no public water supply wells within one-quarter mile Area-of-Review (AoR) around the Federal 11-7-9-18 well.

Technical Publication 92; State of Utah, Department of Natural Resources, cites the base of Underground Sources of Drinking Water (USDW) in the Uinta Formation approximately 322 feet below the ground surface at this location. As there is no definitive data relative to the potential of the Uinta Formation to be a USDW below the depth of 322 feet, the USEPA delineates the Uinta Formation to be a potential USDW to its base of 1,279 feet (top of the Green River Formation as interpreted from a Newfield-provided map).

Throughout the Greater Monument Butte Field area undergoing enhanced oil recovery operations, water analyses of the Green River Formation generally exhibit Total Dissolved Solids (TDS) content well in excess of 10,000 mg/l. However, some recent water analyses from the field showed lower TDS values closer to 10,000 mg/l. While rain and surface water recharge into Green River Formation outcrops further south along the Book Cliffs/Roan Cliffs in effect "freshens" the Green River Formation water near those outcrops, in this area of the Monument Butte Field the observed occasional "freshening" is ascribed to the effective dilution of the originally occurring high TDS water from injection of relatively fresh water for enhanced oil recovery operations. Water samples from deeper Mesaverde Formation sands in the nearby Natural Buttes Unit yield highly saline water.

TABLE 2.3
CONFINING ZONES
Federal 11-7-9-18

Formation Name	Formation Lithology	Top (ft)	Base (ft)
Green River	Shale	3,560	3,594

Underground Sources of Drinking Water (USDWs) (TABLE 2.4)

Aquifers or the portions thereof which contain less than 10,000 mg/l total dissolved solids (TDS) and are being or could in the future be used as a source of drinking water are considered to be USDWs. The USDWs in the area of this facility are identified in TABLE 2.4.

Throughout the Greater Monument Butte Field area undergoing enhanced oil recovery operations, water analyses of the Green River Formation generally exhibit Total Dissolved Solids (TDS) content well in excess of 10,000 mg/l. However, some recent water analyses from the field showed lower TDS values closer to 10,000 mg/l. While rain and surface water recharge into Green River Formation outcrops further south along the Book Cliffs/Roan Cliffs in effect "freshens" the Green River Formation water near those outcrops, in this area of the Monument Butte Field the observed occasional "freshening" is ascribed to the effective dilution of the originally in-place high TDS water from injection of relatively fresh water for enhanced oil recovery operations. Water samples from deeper Mesaverde Formation sands in the nearby Natural Buttes Unit yield highly saline water.

The State of Utah "Water Wells and Springs" identifies no public water supply wells within the one-quarter (1/4) mile Area of Review (AOR) around the Federal 11-7-9-18.

Technical Publication No. 92: State of Utah, Department of Natural Resources, cites the base of Underground Sources of Drinking Water (USDW) in the Uinta Formation approximately 322 feet from the surface. However, absent definitive information relative to the water quality of the Uinta Formation, from the depth of 322 feet to the base of the Uinta Formation (1279 feet), the EPA will require, during plugging and abandonment, a cement plug at the base of the Uinta Formation to protect contamination of possible Uinta USDWs.

TABLE 2.4
UNDERGROUND SOURCES OF DRINKING WATER (USDW)
Federal 11-7-9-18

Formation Name	Formation Lithology	Top (ft)	Base (ft)	TDS (mg/l)
Uinta	Interbedded lacustrine sand, shale, and carbonate with fluvial sand and shale.	0	1,279	

PART III. Well Construction (40 CFR 146.22)

The Federal 11-7-9-18 was drilled to a depth of 5865 (KB) feet in the Basal Carbonate Member of the Green River Formation.

Surface Casing (8-5/8 inch) was set at a depth of 317 feet in a 12-1/4 inch hole using 160 sacks of Class "G" cement which was circulated to the surface. Production casing (5-1/2 inch) was set at a depth of 5842 feet (KB) in a 7-7/8 inch hole with 350 sacks of Prem. Lite II and 450 sacks of 50/50 POZ mix. This well construction is considered adequate to protect USDWs.

The EPA calculates the top of cement as 700 feet from the surface. The Cement Bond Log (CBL) identifies the top of cement at 130 feet. CBL analysis does identify adequate 80% bond index cement bond within the confining zone.

The schematic diagram shows enhanced recovery injection perforations in the Douglas Creek Member of the Green River Formation. Additional perforations may be added at a later time between the depths of 3594 feet and the top of the Wasatch Formations (Estimated to be 5880 feet) provided the operator first notifies the Director and later submits an updated well completion report (EPA Form 7520-12) and schematic diagram.

The packer will be set no higher than 100 feet above the top perforation.

TABLE 3.1
WELL CONSTRUCTION REQUIREMENTS
Federal 11-7-9-18

Casing Type	Hole Size (in)	Casing Size (in)	Cased Interval (ft)	Cemented Interval (ft)
Surface	12.25	8.63	0 - 317	0 - 317
Long String	7.88	0.50	0 - 5,843	130 - 5,865
Tubing	5.50	2.88	0 - 5,647	-

The approved well completion plan will be incorporated into the Permit as APPENDIX A and will be binding on the Permittee. Modification of the approved plan is allowed under 40 CFR 144.52(a)(1) provided written approval is obtained from the Director prior to actual modification.

Casing and Cementing (TABLE 3.1)

The well construction plan was evaluated and determined to be in conformance with standard practices and guidelines that ensure well injection does not result in the movement of fluids into USDWs. Well construction details for this "new" injection well is shown in TABLE 3.1.

Remedial cementing may be required if the casing cement is shown to be inadequate by cement bond log or other demonstration of Part II (External) mechanical integrity.

Tubing and Packer

Injection tubing is required to be installed from a packer up to the surface inside the well casing. The packer will be set above the uppermost perforation. The tubing and packer are designed to

prevent injection fluid from coming into contact with the outermost casing.

Tubing-Casing Annulus (TCA)

The TCA allows the casing, tubing and packer to be pressure-tested periodically for mechanical integrity, and will allow for detection of leaks. The TCA will be filled with fresh water treated with a corrosion inhibitor or other fluid approved by the Director.

The tubing/casing annulus must be kept closed at all times so that it can be monitored as required under conditions of the Permit.

Monitoring Devices

The permittee will be required to install and maintain wellhead equipment that allows for monitoring pressures and providing access for sampling the injected fluid. Required equipment may include but is not limited to: 1) shut-off valves located at the wellhead on the injection tubing and on the TCA; 2) a flow meter that measures the cumulative volume of injected fluid; 3) fittings or pressure gauges attached to the injection tubing and the TCA for monitoring the injection and TCA pressure; and 4) a tap on the injection line, isolated by shut-off valves, for sampling the injected fluid.

All sampling and measurement taken for monitoring must be representative of the monitored activity.

PART IV. Area of Review, Corrective Action Plan (40 CFR 144.55)

**TABLE 4.1
AOR AND CORRECTIVE ACTION**

Well Name	Type	Status (Abandoned Y/N)	Total Depth (ft)	TOC Depth (ft)	CAP Required (Y/N)
Federal 10-7-9-18	Producer	No	5,885	62	No
Federal 12-7-9-18	Other	No	5,875	90	No
Federal 14-7-9-18	Producer	No	5,800	0	No
Federal 6-7-9-18	Producer	No	6,200	7	No

TABLE 4.1 lists the wells in the Area of Review ("AOR") and shows the well type, operating status, depth, top of casing cement ("TOC") and whether a Corrective Action Plan ("CAP") is required for the well.

Area Of Review

Applicants for Class I, II (other than "existing" wells) or III injection well Permits are required to identify the location of all known wells within the injection well's Area of Review (AOR) which penetrate the injection zone, or in the case of Class II wells operating over the fracture pressure of the formation, all known wells within the area of review that penetrate formations which may be affected by increased pressure. Under 40 CFR 146.6 the AOR may be a fixed radius of not less than one quarter (1/4) mile or a calculated zone of endangering influence. For Area Permits, a fixed width of not less than one quarter (1/4) mile for the circumscribing area may be used.

Corrective Action Plan

For wells in the AOR which are improperly sealed, completed, or abandoned, the applicant shall develop a Corrective Action Plan (CAP) consisting of the steps or modifications that are necessary to prevent movement of fluid into USDWs.

The CAP will be incorporated into the Permit as APPENDIX F and become binding on the permittee.

PART V. Well Operation Requirements (40 CFR 146.23)

TABLE 5.1
INJECTION ZONE PRESSURES
Federal 11-7-9-18

Formation Name	Depth Used to Calculate MAIP (ft)	Fracture Gradient (psi/ft)	Initial MAIP (psi)
Green River	4,801	0.670	1,105

Approved Injection Fluid

The approved injection fluid is limited to Class II injection well fluids pursuant to 40 CFR § 144.6(b). For disposal wells injecting water brought to the surface in connection with natural gas storage operations, or conventional oil or natural gas production, the fluid may be commingled and the well used to inject other Class II wastes such as drilling fluids and spent well completion, treatment and stimulation fluid. Injection of non-exempt wastes, including unused fracturing fluids or acids, gas plant cooling tower cleaning wastes, service wastes, and vacuum truck and drum rinsate from trucks and drums transporting or containing non-exempt waste, is prohibited.

The proposed injectate will be a blend of culinary water from the Johnson Water district reservoir and/or water via the Green River pipeline, which will be blended with produced Green River water from wells proximate to the Federal 11-7-9-18.

Injection Pressure Limitation

Injection pressure, measured at the wellhead, shall not exceed a maximum calculated to assure that the pressure used during injection does not initiate new fractures or propagate existing fractures in the confining zones adjacent to the USDWs.

The applicant submitted injection fluid density and injection zone data which was used to calculate a formation fracture pressure and to determine the maximum allowable injection pressure (MAIP), as measured at the surface, for this Permit.

TABLE 5.1 lists the fracture gradient for the injection zone and the approved MAIP, determined according to the following formula:

$$FP = [fg - (0.433 * sg)] * d$$

FP = formation fracture pressure (measured at surface)

- fg = fracture gradient (from submitted data or tests)
sg = specific gravity (of injected fluid)
d = depth to top of injection zone (or top perforation)

Injection Volume Limitation

Cumulative injected fluid volume limits are set to assure that injected fluids remain within the boundary of the exempted area. Cumulative injected fluid volume is limited when injection occurs into an aquifer that has been exempted from protection as a USDW.

There will be no restrictions on the cumulative volume or daily volume of authorized Class II fluid to be injected into the approved Green River Formation interval. The Permittee will not exceed the maximum authorized injection pressure of 1105 psig.

Mechanical Integrity (40 CFR 146.8)

An injection well has mechanical integrity if:

1. there is no significant leak in the casing, tubing, or packer (Part I); and
2. there is no significant fluid movement into a USDW through vertical channels adjacent to the injection well bore (Part II).

The Permit prohibits injection into a well which lacks mechanical integrity.

The Permit requires that the well demonstrate mechanical integrity prior to injection and periodically thereafter. A demonstration of mechanical integrity includes both internal (Part I) and external (Part II). The methods and frequency for demonstrating Part I and Part II mechanical integrity are dependent upon well-specific conditions as explained below.

Well construction and site-specific conditions dictate the following requirements for Mechanical Integrity (MI) demonstrations:

Part I MI: Internal MI will be demonstrated prior to beginning injection. Since this well is constructed with a standard casing, tubing, and packer configuration, a successful mechanical integrity test is required to take place at least once every five years. A demonstration of Part I MI is also required prior to resuming injection following any workover operation that affects the casing, tubing, or packer. Part I MI may be demonstrated by a standard tubing-casing annulus pressure test using the maximum permitted injection pressure or 1000 psi, whichever is less, with a ten-percent or less pressure loss over thirty minutes.

PART II MI: The CBL indicates that cement does not meet minimum requirements needed to demonstrate zone isolation (at least 18 feet of continuous 80% bond, or better) through the Confining Zone. Therefore, further testing for Part II MI will be required prior to injection and at least once every five years thereafter. The demonstration shall be by Temperature Survey or other approved test. Approved tests for demonstrating Part II MI include a Temperature Survey, Noise Log or Oxygen Activation Log, and Region 8 may also accept results of a Radioactive Tracer Survey under certain circumstances.

PART VI. Monitoring, Recordkeeping and Reporting Requirements

Injection Well Monitoring Program

At least once a year the permittee must analyze a sample of the injected fluid for total dissolved solids (TDS), specific conductivity, pH, and specific gravity. This analysis shall be reported to EPA annually as part of the Annual Report to the Director. Any time a new source of injected fluid is added, a fluid analysis shall be made of the new source.

Instantaneous injection pressure, injection flow rate, cumulative fluid volume and TCA pressures must be observed on a weekly basis. A recording, at least once every thirty (30) days, must be made of the injection pressure, annulus pressure, monthly injection flow rate and cumulative fluid volume. This information is required to be reported annually as part of the Annual Report to the Director.

PART VII. Plugging and Abandonment Requirements (40 CFR 146.10)

Plugging and Abandonment Plan

Prior to abandonment, the well shall be plugged in a manner that isolates the injection zone and prevents movement of fluid into or between USDWs, and in accordance with any applicable Federal, State or local law or regulation. Tubing, packer and other downhole apparatus shall be removed. Cement with additives such as accelerators and retarders that control or enhance cement properties may be used for plugs; however, volume-extending additives and gel cements are not approved for plug use. Plug placement shall be verified by tagging. Plugging gel of at least 9.6 lb/gal shall be placed between all plugs. A minimum 50 ft surface plug shall be set inside and outside of the surface casing to seal pathways for fluid migration into the subsurface. Within sixty (60) days after plugging the owner or operator shall submit Plugging Record (EPA Form 7520 13) to the Director. The Plugging Record must be certified as accurate and complete by the person responsible for the plugging operation. The plugging and abandonment plan is described in Appendix E of the Permit.

See diagram.

The well shall be plugged in a manner that isolates the injection zone and prevents movement of fluid into or between USDWs and in accordance with other applicable Federal, State, or local law or regulation. Tubing, packers, and any downhole apparatus shall be removed. Class A, C, G, and H cements, with additives such as accelerators and retarders that control or enhance cement properties, may be used for plugs. However, volume extending additives and gel cements are not approved for plug use. Plug placement shall be verified by tagging. Plugging gel of at least 9.2 lb/gal shall be placed between all plugs. Within sixty days after plugging, the owner or operator shall submit Plugging Record (EPA Form 7520-13) to the Director. The Plugging Record must be certified as accurate and complete by the person responsible for the plugging operation. At a minimum, the following plugs are required:

PLUG NO. 1: Seal injection zone: Set a cast iron bridge plug (CIBP) no more than 50 feet above the top perforation. Place at least twenty feet of cement plug on top of the CIBP.

PLUG NO. 2: Seal Mahogany Shale and Trona intervals: Squeeze a cement plug on the backside of the 5-1/2 inch casing across the Trona zone and the Mahogany Shale approximately 2768 to 2815 feet (unless pre-existing backside cement precludes cement-squeezing this interval) followed by a minimum 145-foot balanced cement plug inside the 5-1/2 inch casing across the Trona zone and Mahogany Shale, approximately 2768 to 2815 feet.

PLUG NO. 3: Seal USDWs: Squeeze a cement plug (1179 to 1279 feet) on the backside of the 5-

1/2 inch casing across the base of the Uinta Formation (unless pre-existing backside cement precludes cement-squeezing this interval), followed by a minimum 100-foot balanced cement plug inside the 5-1/2 inch casing across the base of the Uinta Formation, approximately 1179 to 1279 feet.

PLUG NO. 4: Seal surface: Set a Class "G" cement plug within the 5-1/2 inch casing to 372 feet and up the 5-1/2 inch by 8-5/8 inch casings annulus to the surface.

PART VIII. Financial Responsibility (40 CFR 144.52)

Demonstration of Financial Responsibility

The permittee is required to maintain financial responsibility and resources to close, plug, and abandon the underground injection operation in a manner prescribed by the Director. The permittee shall show evidence of such financial responsibility to the Director by the submission of a surety bond, or other adequate assurance such as financial statements or other materials acceptable to the Director. The Regional Administrator may, on a periodic basis, require the holder of a lifetime permit to submit a revised estimate of the resources needed to plug and abandon the well to reflect inflation of such costs, and a revised demonstration of financial responsibility if necessary. Initially, the operator has chosen to demonstrate financial responsibility with:

Annual financial statement that was reviewed and approved by the EPA December 17, 2007.

Financial Statement, received April 22, 2005

Evidence of continuing financial responsibility is required to be submitted to the Director annually.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: <div style="display: flex; justify-content: space-around;">OIL WELL <input checked="" type="checkbox"/>GAS WELL <input type="checkbox"/>OTHER <input type="checkbox"/></div>		5. LEASE DESIGNATION AND SERIAL NUMBER: USA UTU-16540
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: SUNDANCE UNIT
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 1980 FSL 1977 FWL		8. WELL NAME and NUMBER: FEDERAL 11-7-9-18
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: NESW, 7, T9S, R18E		9. API NUMBER: 4304735451
		10. FIELD AND POOL, OR WILDCAT: MONUMENT BUTTE
		COUNTY: UINTAH
		STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARITLY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: - Injection Conversion
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 10/27/2008			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 10/24/08 Margo Smith with the EPA was contacted concerning the initial MIT on the above listed well. Permission was given at that time to perform the test on 10/28/08. On 10/28/08 the csg was pressured up to 1300 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbq pressure was 200 psig during the test. There was not an EPA representative available to witness the test.

EPA# UT21092-07351 API# 43-047-35451

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) <u>Callie Duncan</u>	TITLE <u>Production Clerk</u>
SIGNATURE <u><i>Callie Ross</i></u>	DATE <u>10/30/2008</u>

(This space for State use only)

RECEIVED
NOV 03 2008
DIV. OF OIL, GAS & MINING

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____

Date: 10 / 28 / 08

Test conducted by: Trefley J. Raza

Others present: _____

Well Name: <u>Fed 11-7-946</u>	Type: ER SWD	Status: AC TA UC
Field: <u>Monument Butte</u>		
Location: <u>NE/3W</u> Sec: <u>7</u> T <u>9</u> N <u>10</u> R <u>18</u> E/W County <u>Gintah</u> State: <u>UT</u>		
Operator: _____		
Last MIT: _____ / _____ / _____		Maximum Allowable Pressure: _____ PSIG

Is this a regularly scheduled test? ☐ Yes ☒ No

Initial test for permit? ☒ Yes ☐ No

Test after well rework? ☐ Yes ☒ No

Well injecting during test? ☐ Yes ☒ No

If Yes, rate: N/A bpd

Pre-test casing/tubing annulus pressure: 0 psig

MIT DATA TABLE	Test #1	Test #2	Test #3
TUBING	PRESSURE		
Initial Pressure	<u>200</u> psig	psig	psig
End of test pressure	<u>200</u> psig	psig	psig
CASING / TUBING	ANNULUS PRESSURE		
0 minutes	<u>1300</u> psig	psig	psig
5 minutes	<u>1300</u> psig	psig	psig
10 minutes	<u>1300</u> psig	psig	psig
15 minutes	<u>1300</u> psig	psig	psig
20 minutes	<u>1300</u> psig	psig	psig
25 minutes	<u>1300</u> psig	psig	psig
30 minutes	<u>1300</u> psig	psig	psig
_____ minutes	<u>—</u> psig	psig	psig
_____ minutes	<u>—</u> psig	psig	psig
RESULT	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____




CHART
CHART NO. MP-2500
PORTAGE, INDIANA
USA
METER *MEI*
CHART PUT ON *11-7-16*
LOCATION *New York*
REMARKS *Clear*
TAKEN BY *W. J. B.*

FEDERAL 11-7-9-18
8/1/2008 To 12/30/2008

10/24/2008 Day: 1**Conversion**

Stone #5 on 10/23/2008 - MIRU Stone #5. RU HO trk to annulus & pump 70 BW @ 250°F. RD pumping unit & unseat rod pump. Flush tbg & rods W/ 40 BW @ 250°F. Re-seat pump, soft joint rod string & strip off flow-T. Fill tbg W/ 3 BW & pressure test to 3000 psi. Retrieve rod string & unseat pump. LD 2 rods. SIWFN due to blown hydraulic hose.

10/25/2008 Day: 2**Conversion**

Stone #5 on 10/24/2008 - LD rod sting & pump. Re-flush rod w/ 40 bbls of wtr on TOH. ND WH. Release TA. NU BOP. Talley out of hole w/ tbg breaking & re-doping every connection (152 jts out). LD 28 jts of tbg on trailer. SIWFN

10/27/2008 Day: 3**Conversion**

Western #1 on 10/26/2008 - MU & TIH W/ injection string as follows: new Weatherford 5 1/2" Arrowset 1-X pkr (W/ W.L. re-entry guide & hardened steel slips), new 2 7/8 SN & 152 jts 2 7/8 8rd 6.5# J-55 tbg. RU HO trk & pump 15 bbl pad. Drop standing valve & pump to SN. Pressure up on tbg to 3000 psi. Held solid for 30 minutes. RIH W/ overshot on sdline. Latch onto & pull standing valve. ND BOP & land tbg on flange. Mix 15 gals Multi-Chem C-6031 & 5 gals B-8625 in 75 bbls fresh wtr. RU HO trk & pump dn annulus @ 90°F. PU on tbg & set pkr W/ SN @ 4763', CE @ 4767' & EOT @ 4772'. Land tbg W/ 15,000# tension. NU wellhead. Pressure test casing & pkr to 1360 psi. Bump pressure several times & monitor. Leave pressure on annulus overnight.

10/28/2008 Day: 4**Conversion**

Rigless on 10/27/2008 - Check annulus pressure--at 1350 psi. Leave pressure on well. RDMOSU. Well ready for MIT.

10/29/2008 Day: 5**Conversion**

Rigless on 10/28/2008 - On 10/24/08 Margo Smith with the EPA was contacted concerning the initial MIT on the above listed well (Fed 11-7-9-18). Permission was given at that time to perform the test on 10/28/08. On 10/28/08 the csg was pressured up to 1300 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbg pressure was 200 psig during the test. There was not an EPA representative available to witness the test. EPA# UT21092-07351 API# 43-047-35451



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 8

1595 Wynkoop Street
DENVER, CO 80202-1129
Phone 800-227-8917
<http://www.epa.gov/region08>

NOV 25 2008

Ref: 8P-W-GW

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Michael Guinn
District Manager
Newfield Production Company
Route 3 – Box 3630
Myton, UT 84052

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

RECEIVED
DEC 02 2008
DIV. OF OIL, GAS & MINING

9S 18E 7
RE: 180-Day Limited Authorization to Inject
Federal 11-7-9-18 Well
EPA Permit No. UT21092-07351
Uintah County, UT
API #43-047-35451

Dear Mr. Guinn:

The Newfield Production Company (Newfield) letter with attached information was received by the Environmental Protection Agency (EPA), Region 8, on November 3, 2008. The submittal satisfactorily completed the **Prior to Commencing Injection** requirements for Final Class II Underground Injection Control Permit UT21092-07351, effective July 23, 2008. The Part I (Internal) Mechanical Integrity Test (MIT), Well Rework Record (EPA Form No. 7520-12), schematic diagram, and calculated pore pressure were reviewed and approved by EPA on November 12, 2008.

As of the date of this letter, Newfield is authorized to commence injection into Federal 11-7-9-18 at a maximum allowable injection pressure (MAIP) of **1,105 psig** for a limited period of time.

Because the cement bond log submitted for this well did not show an adequate interval of 80% or greater bond index through the confining zone above the injection zone, Newfield is required to demonstrate Part II (External) Mechanical Integrity (Part II MI) within a 180-day period from the date that injection begins. Approved tests include temperature survey, noise log or oxygen activation log, and Region 8 may accept results of a Radioactive Tracer Survey. The Part II MIT shall be demonstrated at least once every five years. This 180-day period allows time for injection zone pressure to elevate prior to demonstrating Part II MI, which is necessary because it may be underpressured from previous oil production, and the Part II MI tests rely on elevated formation pressure.

Newfield must receive prior authorization from the Director in order to inject at pressures greater than the permitted MAIP during any test. Please note that the maximum pressure used during the Part II MI test may become the new MAIP because Part II MI was demonstrated at that pressure. Therefore, it may be advantageous to run a step rate test prior to conducting the Part II MI test. Should Newfield apply for an increase to the MAIP at a later date, the demonstration of Part II MI must also be conducted at that time.

Please remember that it is Newfield's responsibility to be aware of and to comply with all conditions of Permit UT21092-07551 from the Federal 11-7-9-18 injection well.

If you have questions regarding the above action, please call Bruce Suchomel at 303-312-6001 or T-800-227-8917, ext. 312-6001. Test logs from the Part II MI test should be mailed directly to the attention of Bruce Suchomel, at the letterhead address citing **Mail Code: 8P-W-GW** very prominently.

Sincerely,



Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

cc: Uintah & Ouray Business Committee, Ute Indian Tribe:

Curtis Cesspooch, Chairman
Irene Cuch, Vice-Chairwoman
Frances Poowegup, Councilwoman
Ronald Groves, Councilman
Phillip Chimburas, Councilman
Steven Cesspooch, Councilman

Daniel Picard, Superintendent
Uintah & Ouray Indian Agency
U.S. Bureau of Indian Affairs

Michelle Sabori, Acting Director
GAP 106
Ute Indian Tribe

Shaun Chapoose, Director
Land Use Dept.
Ute Indian Tribe

Elaine Willie, Gap Coordinator
Land Use Department
Ute Indian Tribe

Larry Love, Director
Energy & Minerals Dept.
Ute Indian Tribe

Gilbert Hunt, Associate Director
Utah Division of Oil, Gas, and Mining

Fluid Minerals Engineering Department
U.S. Bureau of Land Management
Vernal, Utah

Eric Sundberg, Regulatory Analyst
Newfield Exploration Company

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL:		5. LEASE DESIGNATION AND SERIAL NUMBER:	
OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <u>WI</u>		USA UTU-16540	
2. NAME OF OPERATOR:		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:	
NEWFIELD PRODUCTION COMPANY		SUNDANCE UNIT	
3. ADDRESS OF OPERATOR:		8. WELL NAME and NUMBER:	
Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		FEDERAL 11-7-9-18	
4. LOCATION OF WELL:		9. API NUMBER:	
FOOTAGES AT SURFACE: 1980 FSL 1977 FWL		4304735451	
OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: NESW, 7, T9S, R18E		10. FIELD AND POOL, OR WILDCAT:	
		MONUMENT BUTTE	
		COUNTY: UINTAH	
		STATE: UT	

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will <u>12/08/2008</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Change status put well on injection
	<input checked="" type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above reference well was put on injection at 8:00 AM on 12-8-08.

Accepted by the
Utah Division of
Oil, Gas and Mining
RECORD ONLY

NAME (PLEASE PRINT) Kathy Chapman	TITLE Office Manager
SIGNATURE <u>Kathy Chapman</u>	DATE 12/11/2008

(This space for State use only)

RECEIVED

DEC 15 2008

DIV. OF OIL, GAS & MINING

E



UNITED STATES ENVIRONMENTAL PROTECTION AGENCY
REGION 8

1595 Wynkoop Street
Denver, CO 80202-1129
Phone 800-227-8917
<http://www.epa.gov/region08>

Ref: 8P-W-GW

JUN 18 2009

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY

CERTIFIED MAIL
RETURN RECEIPT REQUESTED

Michael Guinn
District Manager
Newfield Production Company
Route 3-Box 3630
Myton, UT 84502

RECEIVED

JUN 22 2009

DIV. OF OIL, GAS & MINING

RE: **Authorization to Continue Injection**
EPA UIC Permit UT21092-07351
Well: Federal 11-7-9-18
Uintah County, Utah
API # 43-047-35451

Dear Mr. Guinn:

95 18E 7

The Region 8 Ground Water Program office of the Environmental Protection Agency (EPA) received the results from the April 29, 2009 Radioactive Tracer Survey (RTS) used to demonstrate no significant upward migration of injection fluids behind casing from the injection zone. The results of the RTS were reviewed and approved on June 2, 2009 and EPA has determined that the test adequately demonstrated that injected fluids will remain in the authorized injection interval at or below the Maximum Authorized Injection Pressure (MAIP) of 1,105 psig.

EPA hereby authorizes continued injection into Federal 11-7-9-18 under the terms and conditions of EPA UIC Permit UT21092-07351 at an MAIP of 1,105 psig.

You may apply for a higher maximum allowable injection pressure at a later date. Your application should be accompanied by the interpreted results from a Step-Rate Test (SRT) that measures the formation fracture pressure and the fracture gradient at this location. A current copy of EPA Guidelines for running and interpreting a SRT will be sent upon request. Should the SRT result in approval of a higher maximum allowable injection pressure, a new RTS must be run to show that the injected fluids will remain in the authorized injection interval at the higher pressure. Please note that to use a pressure greater than the MAIP of 1,105 psig during a SRT or RTS you must receive prior written authorization from the Director.


As of this approval, responsibility for Permit Compliance and Enforcement is transferred to Region 8 UIC Technical Enforcement Program office. Therefore, please direct all future notification, reporting, monitoring and compliance correspondence to the following address, referencing your well name and UIC Permit number on all correspondence regarding this well:

FOR RECORD ONLY

US.EPA, Region 8
Attn: Nathan Wiser
MC: ENF-UFO
1595 Wynkoop Street
Denver, CO 80202

Please be reminded that it is your responsibility to be aware of and to comply with all conditions of your Permit. If you have any questions regarding this approval, please call Jason Deardorff at 800-227-8917 (ext. 312-6583). For questions regarding notification, testing, monitoring, reporting or other Permit requirements, Nathan Wiser of the UIC Technical Enforcement Program may be reached by calling 800-227-8917 (ext. 312-6211).

Sincerely,



for Stephen S. Tuber
Assistant Regional Administrator
Office of Partnerships and Regulatory Assistance

cc:

Uintah & Ouray Business Committee
Curtis Cesspooch, Chairman
Ronald Groves, Councilman
Irene Cuch, Vice-Chairwoman
Steven Cesspooch, Councilman
Phillip Chimburas, Councilman
Frances Poowegup, Councilwoman

Daniel Picard
BIA - Uintah & Ouray Indian Agency

Ferron Secakuku
Director, Natural Resources
Ute Indian Tribe

Larry Love
Director of Energy & Minerals Dept.
Ute Indian Tribe

Gil Hunt
Associate Director
Utah Division of Oil, Gas, and Mining

Fluid Minerals Engineering Office
BLM - Vernal Office

Eric Sundberg
Regulatory Analyst
Newfield Exploration Company

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
USA UTU-16540

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
GMBU

1. TYPE OF WELL:

OIL WELL ☒ GAS WELL ☐ OTHER

8. WELL NAME and NUMBER:
FEDERAL 11-7-9-18

2. NAME OF OPERATOR:

NEWFIELD PRODUCTION COMPANY

9. API NUMBER:

4304735451

3. ADDRESS OF OPERATOR:

Route 3 Box 3630

CITY Myton

STATE UT

ZIP 84052

PHONE NUMBER

435.646.3721

10. FIELD AND POOL, OR WILDCAT:

GREATER MB UNIT

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 1980 FSL 1977 FWL

COUNTY: UINTAH

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: NESW, 7, T9S, R18E

STATE: UT

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 11/03/2010	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Step Rate Test	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

A step rate test was conducted on the subject well on November 3, 2010. Results from the test indicate that the fracture gradient is .0692 psi/ft. Therefore, Newfield is requesting that the maximum allowable injection pressure (MAIP) be changed from 1105 psi to 1210 psi.

EPA: UT21092-07351 API: 43-047-35451

**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE PRINT) Lucy Chavez-Naupoto

TITLE Administrative Assistant

SIGNATURE

DATE 11/10/2010

(This space for State use only)

RECEIVED
NOV 16 2010
DIV. OF OIL, GAS & MINING

Step Rate Test (SRT) Analysis

Date: 11/04/2010

Operator:

Newfield Production Company

Well:

Federal 11-7-9-18

Permit #:

UT21092-07351

Enter the following data :

Specific Gravity (sg) of injectate = 1.015 g/cc
Depth to top perforation (D) = 4801 feet 4801
Top of permitted injection zone depth (blank=use top perforation to calculate fg) = _____ feet
Estimated Formation Parting Pressure (Pfp) from SRT chart = 1218 psi
Instantaneous Shut In Pressure (ISIP) from SRT = 1213 psi 1218
Bottom Hole Parting Pressure (Pbhp) from downhole pressure recorder = _____ psi no downhole

Part One - Calculation of Fracture Gradient (fg)

Calculated Fracture Gradient = 0.692 psi/ft.

where: $fg = Pbhp / D$ (Note: this formula uses the downhole recorded bottom hole parting pressure if available) = 1213

D = depth used = 4801

Pbhp used = 3323

Calculated Bottom Hole Parting Pressure (Pbhp) = 3323 psi 3323.015

to calculate Bottom Hole Parting Pressure (Pbhp) = Formation Fracture Pressure (ISIP or Pfp) + (0.433 * SG * D)

(Uses lesser of ISIP or Pfp) Value used = 1213

Part Two - Calculation of Maximum Allowable Injection Pressure (MAIP)


Maximum Allowable Injection Pressure (MAIP) = 1210 psig

D = depth used = 4801

MAIP = $[fg \cdot (0.433 \cdot SG)] \cdot D = 1212.277$


(rounded down to nearest 5 psig)

Federal 11-7-9-18
Greater Monument Butte Unit
Step Rate Test
November 3, 2010



Start Pressure: 996 psi
Instantaneous Shut In Pressure (ISIP): 1213 psi
Top Perforation: 4801 feet
Fracture pressure (Pfp): 1218 psi
FG: 0.693 psi/ft


Step	Rate(bpd)	Pressure(psi)
1	250	1060
2	500	1148
3	750	1218
4	1000	1242
5	1250	1267
6	1500	1288



Report Name:	PrTemp1000 Data Table
Report Date:	Nov 04, 2010 07:39:01 AM MDT
File Name:	C:\Program Files\PTC® Instruments 2.00\Federal 11-7-9-18 SRT (11-3-10).csv
Title:	Federal 11-7-9-18 SRT (11-3-10)
Device:	PrTemp1000 - Temperature and Pressure Recorder
Hardware Revision:	REV2C (64K)
Serial Number:	M75866
Device ID:	PrTemp
Data Start Date:	Nov 03, 2010 05:30:00 AM MDT
Data End Date:	Nov 03, 2010 12:00:01 PM MDT
Reading Rate:	2 Seconds
Readings:	1 to 79 of 79
Last Calibration Date:	May 22, 2009
Next Calibration Date:	May 22, 2010

<u>Reading</u>	<u>Date and Time (MDT)</u>	<u>Absolute Pressure</u>	<u>Annotation</u>
1	Nov 03, 2010 05:30:00 AM	996.400	PSIA
2	Nov 03, 2010 05:34:59 AM	996.800	PSIA
3	Nov 03, 2010 05:40:00 AM	995.600	PSIA
4	Nov 03, 2010 05:44:59 AM	996.600	PSIA
5	Nov 03, 2010 05:50:01 AM	996.200	PSIA
6	Nov 03, 2010 05:55:00 AM	996.200	PSIA
7	Nov 03, 2010 06:00:00 AM	995.600	PSIA
8	Nov 03, 2010 06:05:00 AM	1035.600	PSIA
9	Nov 03, 2010 06:10:00 AM	1042.600	PSIA
10	Nov 03, 2010 06:15:00 AM	1043.400	PSIA
11	Nov 03, 2010 06:19:59 AM	1044.800	PSIA
12	Nov 03, 2010 06:25:00 AM	1045.800	PSIA
13	Nov 03, 2010 06:30:05 AM	1049.400	PSIA
14	Nov 03, 2010 06:35:01 AM	1049.800	PSIA
15	Nov 03, 2010 06:40:00 AM	1052.800	PSIA
16	Nov 03, 2010 06:45:01 AM	1054.600	PSIA
17	Nov 03, 2010 06:49:59 AM	1057.200	PSIA
18	Nov 03, 2010 06:55:00 AM	1058.200	PSIA
19	Nov 03, 2010 06:59:59 AM	1059.800	PSIA
20	Nov 03, 2010 07:04:59 AM	1103.600	PSIA
21	Nov 03, 2010 07:09:59 AM	1111.600	PSIA
22	Nov 03, 2010 07:15:00 AM	1116.400	PSIA
23	Nov 03, 2010 07:20:01 AM	1121.400	PSIA
24	Nov 03, 2010 07:25:00 AM	1124.000	PSIA
25	Nov 03, 2010 07:30:00 AM	1129.800	PSIA
26	Nov 03, 2010 07:35:00 AM	1134.600	PSIA
27	Nov 03, 2010 07:40:01 AM	1138.400	PSIA
28	Nov 03, 2010 07:44:59 AM	1137.600	PSIA
29	Nov 03, 2010 07:50:00 AM	1142.400	PSIA
30	Nov 03, 2010 07:54:59 AM	1145.400	PSIA
31	Nov 03, 2010 07:59:59 AM	1147.800	PSIA
32	Nov 03, 2010 08:05:00 AM	1178.400	PSIA
33	Nov 03, 2010 08:09:59 AM	1188.200	PSIA
34	Nov 03, 2010 08:15:00 AM	1189.400	PSIA
35	Nov 03, 2010 08:19:59 AM	1193.600	PSIA
36	Nov 03, 2010 08:25:01 AM	1197.200	PSIA
37	Nov 03, 2010 08:29:59 AM	1200.600	PSIA
38	Nov 03, 2010 08:35:00 AM	1206.200	PSIA
39	Nov 03, 2010 08:39:59 AM	1207.800	PSIA
40	Nov 03, 2010 08:44:59 AM	1208.200	PSIA
41	Nov 03, 2010 08:50:00 AM	1209.200	PSIA
42	Nov 03, 2010 08:55:00 AM	1218.200	PSIA
43	Nov 03, 2010 09:00:00 AM	1217.800	PSIA
44	Nov 03, 2010 09:04:59 AM	1238.400	PSIA
45	Nov 03, 2010 09:10:01 AM	1238.000	PSIA
46	Nov 03, 2010 09:15:00 AM	1239.000	PSIA
47	Nov 03, 2010 09:19:59 AM	1242.200	PSIA
48	Nov 03, 2010 09:24:59 AM	1243.400	PSIA
49	Nov 03, 2010 09:29:59 AM	1238.600	PSIA
50	Nov 03, 2010 09:35:00 AM	1240.600	PSIA
51	Nov 03, 2010 09:40:00 AM	1239.600	PSIA
52	Nov 03, 2010 09:45:01 AM	1239.200	PSIA
53	Nov 03, 2010 09:49:59 AM	1242.200	PSIA
54	Nov 03, 2010 09:55:01 AM	1242.600	PSIA
55	Nov 03, 2010 10:00:00 AM	1242.000	PSIA
56	Nov 03, 2010 10:04:59 AM	1262.800	PSIA
57	Nov 03, 2010 10:09:59 AM	1261.400	PSIA
58	Nov 03, 2010 10:15:00 AM	1263.800	PSIA
59	Nov 03, 2010 10:20:01 AM	1263.200	PSIA
60	Nov 03, 2010 10:25:00 AM	1267.600	PSIA

61	Nov 03, 2010 10:30:03 AM	1265.200	PSIA
62	Nov 03, 2010 10:35:00 AM	1267.800	PSIA
63	Nov 03, 2010 10:40:01 AM	1269.400	PSIA
64	Nov 03, 2010 10:45:00 AM	1263.000	PSIA
65	Nov 03, 2010 10:50:00 AM	1267.800	PSIA
66	Nov 03, 2010 10:55:00 AM	1266.800	PSIA
67	Nov 03, 2010 11:00:00 AM	1267.200	PSIA
68	Nov 03, 2010 11:05:01 AM	1277.200	PSIA
69	Nov 03, 2010 11:10:00 AM	1283.000	PSIA
70	Nov 03, 2010 11:15:01 AM	1285.000	PSIA
71	Nov 03, 2010 11:19:59 AM	1281.200	PSIA
72	Nov 03, 2010 11:25:01 AM	1286.800	PSIA
73	Nov 03, 2010 11:30:00 AM	1283.600	PSIA
74	Nov 03, 2010 11:35:00 AM	1287.400	PSIA
75	Nov 03, 2010 11:40:00 AM	1285.400	PSIA
76	Nov 03, 2010 11:45:00 AM	1284.400	PSIA
77	Nov 03, 2010 11:50:01 AM	1287.000	PSIA
78	Nov 03, 2010 11:55:00 AM	1288.400	PSIA
79	Nov 03, 2010 12:00:01 PM	1288.000	PSIA



Report Name: PrTemp1000 Data Table
 Report Date: Nov 04, 2010 07:38:52 AM MDT
 File Name: C:\Program Files\PTC® Instruments 2.00\Federal 11-7-9-18 ISIP (11-3-10).csv
 Title: Federal 11-7-9-18 ISIP (11-3-10)
 Device: PrTemp1000 - Temperature and Pressure Recorder
 Hardware Revision: REV2C (64K)
 Serial Number: M75866
 Device ID: PrTemp
 Data Start Date: Nov 03, 2010 12:00:12 PM MDT
 Data End Date: Nov 03, 2010 12:30:12 PM MDT
 Reading Rate: 2 Seconds
 Readings: 1 to 31 of 31
 Last Calibration Date: May 22, 2009
 Next Calibration Date: May 22, 2010

<u>Reading</u>	<u>Date and Time (MDT)</u>	<u>Absolute Pressure</u>	<u>Annotation</u>
1	Nov 03, 2010 12:00:12 PM	1284.200	PSIA
2	Nov 03, 2010 12:01:12 PM	1213.000	PSIA
3	Nov 03, 2010 12:02:12 PM	1216.800	PSIA
4	Nov 03, 2010 12:03:12 PM	1213.600	PSIA
5	Nov 03, 2010 12:04:11 PM	1210.600	PSIA
6	Nov 03, 2010 12:05:11 PM	1208.800	PSIA
7	Nov 03, 2010 12:06:12 PM	1206.600	PSIA
8	Nov 03, 2010 12:07:12 PM	1204.400	PSIA
9	Nov 03, 2010 12:08:13 PM	1203.000	PSIA
10	Nov 03, 2010 12:09:13 PM	1201.800	PSIA
11	Nov 03, 2010 12:10:13 PM	1200.800	PSIA
12	Nov 03, 2010 12:11:13 PM	1199.600	PSIA
13	Nov 03, 2010 12:12:12 PM	1197.600	PSIA
14	Nov 03, 2010 12:13:12 PM	1196.600	PSIA
15	Nov 03, 2010 12:14:12 PM	1195.800	PSIA
16	Nov 03, 2010 12:15:12 PM	1195.000	PSIA
17	Nov 03, 2010 12:16:12 PM	1194.000	PSIA
18	Nov 03, 2010 12:17:12 PM	1193.000	PSIA
19	Nov 03, 2010 12:18:11 PM	1191.800	PSIA
20	Nov 03, 2010 12:19:11 PM	1191.200	PSIA
21	Nov 03, 2010 12:20:12 PM	1190.200	PSIA
22	Nov 03, 2010 12:21:11 PM	1189.600	PSIA
23	Nov 03, 2010 12:22:12 PM	1188.800	PSIA
24	Nov 03, 2010 12:23:12 PM	1188.000	PSIA
25	Nov 03, 2010 12:24:13 PM	1187.400	PSIA
26	Nov 03, 2010 12:25:12 PM	1186.800	PSIA
27	Nov 03, 2010 12:26:12 PM	1185.800	PSIA
28	Nov 03, 2010 12:27:11 PM	1185.400	PSIA
29	Nov 03, 2010 12:28:12 PM	1184.800	PSIA
30	Nov 03, 2010 12:29:11 PM	1184.400	PSIA
31	Nov 03, 2010 12:30:12 PM	1183.400	PSIA

Federal 11-7-9-18 Rate Sheet (11-3-10)

<i>Step # 1</i>	Time:	6:05	6:10	6:15	6:20	6:25	6:30
	Rate:	250.6	250.6	250.5	250.5	250.5	250.5
	Time:	6:35	6:40	6:45	6:50	6:55	7:00
	Rate:	250.4	250.4	250.4	250.4	250.3	250.3
<i>Step # 2</i>	Time:	7:05	7:10	7:15	7:20	7:25	7:30
	Rate:	500.4	500.4	500.4	500.4	500.3	500.3
	Time:	7:35	7:40	7:45	7:50	7:55	8:00
	Rate:	500.3	500.3	500.2	500.2	500.2	500.2
<i>Step # 3</i>	Time:	8:05	8:10	8:15	8:20	8:25	8:30
	Rate:	750.5	750.5	750.5	750.5	750.4	750.4
	Time:	8:35	8:40	8:45	8:50	8:55	9:00
	Rate:	750.4	750.3	750.3	750.2	750.2	750.2
<i>Step # 4</i>	Time:	9:05	9:10	9:15	9:20	9:25	9:30
	Rate:	1000.5	1000.5	1000.5	1000.5	1000.5	1000.3
	Time:	9:35	9:40	9:45	9:50	9:55	10:00
	Rate:	1000.3	1000.2	1000.2	1000.2	1000.1	1000.1
<i>Step # 5</i>	Time:	10:05	10:10	10:15	10:20	10:25	10:30
	Rate:	1250.4	1250.4	1250.4	1250.3	1250.3	1250.3
	Time:	10:35	10:40	10:45	10:50	10:55	11:00
	Rate:	1250.2	1250.2	1250.2	1250.2	1250.1	1250.1
<i>Step # 6</i>	Time:	11:05	11:10	11:15	11:20	11:25	11:30
	Rate:	1500.5	1500.5	1500.4	1500.4	1500.4	1500.3
	Time:	11:35	11:40	11:45	11:50	11:55	12:00
	Rate:	1500.3	1500.3	1500.3	1500.2	1500.2	1500.2

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-16540
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: FEDERAL 11-7-9-18
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1980 FSL 1977 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NESW Section: 07 Township: 09.0S Range: 18.0E Meridian: S		9. API NUMBER: 43047354510000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: 8 MILE FLAT NORTH
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/27/2013	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	OTHER: <input type="text" value="5 YR MIT"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. 5 YR MIT performed on the above listed well. On 09/27/2013 the casing was pressured up to 1400 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tbq pressure was 972 psig during the test. There was not an EPA representative available to witness the test. EPA #UT22197-07351		
NAME (PLEASE PRINT) Lucy Chavez-Naupoto		PHONE NUMBER 435 646-4874
SIGNATURE N/A		TITLE Water Services Technician
DATE 10/4/2013		Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 24, 2013

Mechanical Integrity Test

Casing or Annulus Pressure Mechanical Integrity Test

U.S. Environmental Protection Agency
Underground Injection Control Program
999 18th Street, Suite 500 Denver, CO 80202-2466

EPA Witness: _____ Date: 9/27/2013
Test conducted by: Bart Stubbs
Others present: _____

Well Name: <u>Fed 11-7-9-18</u>	Type: ER SWD	Status: AC TA UC
Field: <u>Monument Butte</u>		
Location: <u>11</u> Sec: <u>7</u> T <u>9</u> N <u>18</u> R <u>18</u> W	County: <u>Uintah</u> State: <u>UT</u>	
Operator: <u>Newfield Production</u>		
Last MIT: <u>1</u>	Maximum Allowable Pressure: <u>1030</u>	PSIG

Is this a regularly scheduled test? ☒ Yes ☐ No
Initial test for permit? ☐ Yes ☒ No
Test after well rework? ☐ Yes ☒ No
Well injecting during test? ☐ Yes ☒ No If Yes, rate: _____ bpd

Pre-test casing/tubing annulus pressure: 0/972 psig

MIT DATA TABLE	Test #1	Test #2	Test #3
TUBING	PRESSURE		
Initial Pressure	<u>972</u> psig	psig	psig
End of test pressure	<u>972</u> psig	psig	psig
CASING / TUBING	ANNULUS	PRESSURE	
0 minutes	<u>1400</u> psig	psig	psig
5 minutes	<u>1400</u> psig	psig	psig
10 minutes	<u>1400</u> psig	psig	psig
15 minutes	<u>1400</u> psig	psig	psig
20 minutes	<u>1400</u> psig	psig	psig
25 minutes	<u>1400</u> psig	psig	psig
30 minutes	<u>1400</u> psig	psig	psig
_____ minutes	psig	psig	psig
_____ minutes	psig	psig	psig
RESULT	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail	<input type="checkbox"/> Pass <input type="checkbox"/> Fail

Does the annulus pressure build back up after the test? ☐ Yes ☒ No

MECHANICAL INTEGRITY PRESSURE TEST

Additional comments for mechanical integrity pressure test, such as volume of fluid added to annulus and bled back at end of test, reason for failing test (casing head leak, tubing leak, other), etc.:

Signature of Witness: _____

NEWFIELD

Schematic

Well Name: **Federal 11-7-9-18**


Surface Legal Location	API/UWI	Well RC	Lease	State/Province	Field Name	County
07-9S-18E	43047354510000	500150731		Utah	GMBU CTB10	UINTAH
Spud Date	Rig Release Date	On Production Date	Original KB Elevation (ft)	Ground Elevation (ft)	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB)
6/8/2005	6/22/2005	7/15/2005	5,084	5,072		Original Hole - 5,799.0

Most Recent Job

Job Category	Primary Job Type	Secondary Job Type	Job Start Date	Job End Date
Testing		N/A	9/27/2013	9/27/2013

TD: 5,865.0

Vertical - Original Hole, 7/28/2015 9:20:08 AM



NEWFIELD



Newfield Wellbore Diagram Data Federal 11-7-9-18

Surface Legal Location 07-9S-18E		API/UWI 43047354510000		Lease	
County UINTAH	State/Province Utah		Basin	Field Name GMBU CTB10	
Well Start Date 6/8/2005	Spud Date 6/8/2005		Final Rig Release Date 6/22/2005	On Production Date 7/15/2005	
Original KB Elevation (ft) 5,084	Ground Elevation (ft) 5,072	Total Depth (ftKB) 5,865.0	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB) Original Hole - 5,799.0	

Casing Strings

Csg Des	Run Date	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface	6/8/2005	8 5/8	8.097	24.00	J-55	317
Production	6/22/2005	5 1/2	4.950	15.50	J-55	5,843

Cement

String: Surface, 317ftKB 6/10/2005

Cementing Company BJ Services Company	Top Depth (ftKB) 12.0	Bottom Depth (ftKB) 317.1	Full Return?	Vol Cement Ret (bbl)
Fluid Description w/ 2% CaCL2 + 1/4#/sk Cello-Flake	Fluid Type Lead	Amount (sacks) 160	Class G	Estimated Top (ftKB) 12.0

String: Production, 5,843ftKB 6/22/2005

Cementing Company BJ Services Company	Top Depth (ftKB) 130.0	Bottom Depth (ftKB) 5,865.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description w/ 10% gel + 3 % KCL, 3#s /sk CSE + 2# sk/kolseal + 1/2#s/sk Cello Flake	Fluid Type Lead	Amount (sacks) 350	Class Premlite II	Estimated Top (ftKB) 130.0
Fluid Description W/ 2% Gel + 3% KCL, .5%EC1,1/4# sk C.F. 2% gel. 3% SM	Fluid Type Tail	Amount (sacks) 450	Class 50/50 Poz	Estimated Top (ftKB) 3,000.0

Tubing Strings

Tubing Description					Run Date		Set Depth (ftKB)	
Tubing					10/27/2008		4,771.5	
Item Des	Jts	OD (in)	ID (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Blm (ftKB)
Tubing	152	2 7/8	2.441	6.50	J-55	4,751.05	12.0	4,763.1
Pump Seating Nipple		2 7/8	2.441			1.10	4,763.1	4,764.2
Packer		5 1/2	2.441			7.37	4,764.2	4,771.5

Rod Strings

Rod Description		Run Date			Set Depth (ftKB)		
Item Des	Jts	OD (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Blm (ftKB)

Perforation Intervals

Stage#	Zone	Top (ftKB)	Blm (ftKB)	Shot Dens (shots/ft)	Phasing (")	Nom Hole Dia (in)	Date
4	B2 sds, Original Hole	4,801	4,809	4	90	0.430	7/12/2005
3	A1 sds, Original Hole	5,004	5,020	4	90	0.430	7/11/2005
3	A3 sds, Original Hole	5,040	5,047	4	90	0.430	7/11/2005
2	CP1 sds, Original Hole	5,387	5,400	4	90	0.430	7/11/2005
2	CP2 sds, Original Hole	5,456	5,467	4	90	0.430	7/11/2005
1	CP3 sds, Original Hole	5,566	5,590	4	120	0.460	7/1/2005

Stimulations & Treatments

Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbl/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
1	1,300	0.67	25.4	1,211			
2	1,450	0.7	25.5	1,436			
3	1,750	0.78	25.4	1,369			
4	2,250	0.9	25.4	1,811			

Proppant

Stage#	Total Prop Vol Pumped (lb)	Total Add Amount
1		Proppant White Sand 60749 lb
2		Proppant White Sand 69628 lb
3		Proppant White Sand 120297 lb
4		Proppant White Sand 24544 lb